SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyrighted, 1888, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LIX.—No. 2. [NEW SERIES.] NEW YORK, JULY 14, 1888. [$3.00 per Year.

## REPRODUCTION OF ARTICULATE SPEECH AND OTHER SOUNDS.

The transmission of articulate speech—as wonderful and useful as it is—is fully equaled in point of novelty by the instruments for recording, preserving, and reproducing speech. Without doubt, these "speech reproducers" are destined sooner or later to take a large place in business and social transactions. No one who has given the matter a moment's thought will fail to see the utility of a practical machine of this sort.

Leon Scott long ago devised a simple and curious instrument known as the phonautograph, in which the vibrations of a diaphragm were recorded by a stylus upon a smoked cylinder, but it is now known that its record was not autographic, although it conveyed a fair idea of the number and variety of air waves necessary to the production of words and sentences.

Faber's talking machine is curious and interesting on account of being a mechanical imitation of the vocal organs. It is capable of producing articulate speech by the manipulation of a bellows and key.

The first machine to really echo one's own words was the Edison phonograph, which, as originally presented, was not sufficiently effective in its operation to be of any great commercial value, although it contained the germ of the modern talking machine.

The graphophone, which is shown in the annexed engravings, is, as its name indicates, a recorder and reproducer of sounds. It is the invention of Mr. Charles Sumner Tainter, and is the result of several years' experimentation and the subject of many patents, several of which were issued in May, 1886. In its construction, efficiency has, of course, been the first consideration, after which the matters of simplicity, facility of management, and the practical handling of the records or messages have been disposed of.



THE REPRODUCTION OF ARTICULATE SPEECH.

The machine is an exceedingly simple thing. The large illustration shows it as arranged for receiving or recording the message. Fig. 1 shows it as it appears while repeating or reproducing. The frame of the machine consists of end pieces connected by longitudinal rods. In the top of the frame is journaled a fine screw partly inclosed by a tube, the screw being driven through a train of spur wheels from the main shaft journaled in the lower part of the left hand end piece. The main shaft—besides carrying the gearing which moves the feed screw—is provided with a conical chuck. In the opposite end of the frame is journaled a spring-pressed spindle, which also carries a conical chuck of the same form and size as that on the main shaft. The cylinder upon which the speech is to be recorded is received between these chucks, as shown in Fig. 3, and in much the same manner as the bobbin is placed in the bobbin winder of the sewing machine, the cylinder being revolved by frictional contact with the chuck on the main shaft. At the right hand of the instrument is arranged a small rock shaft, provided with a cross arm and two keys by which the driving wheel is thrown into and out of connection with the gearing of the machine.

Upon the tube which incloses the feed screw is placed a saddle (Fig 4), provided with a follower which enters the slot of the tube and engages the feed screw. The saddle carries a diaphragm cell, in which is arranged a diaphragm provided with a cutting stylus which engraves the record in the surface of the cylinder.

To the diaphragm cell is attached a bar or bridge piece of metal, which extends across the face of the diaphragm, but not in contact with it. This device rests upon the record cylinder a little in advance of the cutting stylus, and supports the weight of the diaphragm cell and its attachments. The depth to which the stylus penetrates the surface of the cylinder is regulated and maintained by this arrangement, and as the bridge piece bears upon the cylinder near the point of cutting, the apparatus follows all the irregularities of the re-

(*Continued on page* 23.)



THE GRAPHOPHONE, MR. CHARLES SUMNER TAINTER'S NEW SPEECH RECORDER.

© 1888 SCIENTIFIC AMERICAN, INC.



# Scientific American.

ESTABLISHED 1845.

MUNN & CO., Editors and Proprietors.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, NEW YORK.

O. D. MUNN. A. E. BEACH.

**TERMS FOR THE SCIENTIFIC AMERICAN.**

One copy, one year, for the U. S. or Canada.....$3 00
One copy, six months, for the U. S. or Canada..... 1 50
One copy, one year, to any foreign country belonging to Postal Union, 4 00

Remit by postal or express money order.

**Australia and New Zealand.**—Those who desire to receive the SCIENTIFIC AMERICAN, for a little over one year, may remit £1 in current Colonial bank notes. Address

MUNN & CO., 361 Broadway, corner of Franklin Street, New York.

**The Scientific American Supplement**

is a distinct paper from the SCIENTIFIC AMERICAN. THE SUPPLEMENT is issued weekly. Every number contains 16 octavo pages, uniform in size with SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, $5.00 a year, for U. S. and Canada. $6.00 a year to foreign countries belonging to the Postal Union. Single copies, 10 cents. Sold by all newsdealers throughout the country.

**Combined Rates.**—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year, to any address in U. S. or Canada, on receipt of *seven dollars*.

The safest way to remit is by draft, postal order, express money order, or registered letter.

**Australia and New Zealand.**—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for a little over one year on receipt of £2 current Colonial bank notes.

Address MUNN & CO., 361 Broadway, corner of Franklin Street, New York.

NEW YORK, SATURDAY, JULY 14, 1888.


**Contents.**

(Illustrated articles are marked with an asterisk.)


American Association for the Advancement of Science, meeting of..... 16
American wares in Austria..... 24
Articulate speech, reproduction of*..... 15
Bathing, precautions in..... 25
Bee culture..... 21
Books and publications, new..... 27
British Association meeting..... 25
Business and personal..... 27
Can opener, improved*..... 18
Cars, street, electrical..... 22
Celestial world, the..... 16
Clamp for fruit can covers*..... 18
Comfort and health, seasonable hints for..... 24
Corea by native artists*..... 20
Coupling, car, improved*..... 19
Death by electricity..... 26
Deceptive senses..... 22
Electrical annunciator, improved*18
Electrical resistance of copper at low temperature..... 17
Filter plant of National Water Purifying Company*..... 22
Fishing nets, machine for making*22
Flour yields..... 21
Graphophone, the*..... 15
Handle for cross-cut saws, removable*..... 19
Hay, when to cut..... 21
Holding bed clothes in position, device for*..... 19
How science advances..... 18
Inventions, engineering..... 27
Inventions, index of..... 27
Inventions, miscellaneous..... 27
Iron and steel production..... 17
Machinery in Mexico..... 25
Military notes..... 16
Miscellaneous notes..... 26
Naval cadet, breaking in a..... 21
Naval revolution, the coming..... 19
Petroleum, solid..... 24
Physics, simple experiments in*.. 25
Pipe, tobacco, improved*..... 19
Purifying water by filtration*..... 23
Richard Trevethick..... 17
Roland Duer Irving..... 17
Ship's log, improved*..... 18
Speech recorder, new*..... 15
Sterilized milk as a food..... 24
Stopping leaks in vessels, device for*..... 18
Tool drilling, improved*..... 19
Trans-Caspian railway..... 17
Whistling speech..... 17


TABLE OF CONTENTS OF

## SCIENTIFIC AMERICAN SUPPLEMENT

## No. 654

**For the Week Ending July 14, 1888.**

Price 10 cents. For sale by all newsdealers.


PAGE

I. CHEMISTRY.—A New Lecture Apparatus for Making Sulphuric Anhydride.—By Dr. W. R. HODGKINSON and F. K. LOWNDES, F.C.S.—The oxidation of sulphurous oxide in presence of spongy platinum.—1 illustration..... 10453
The New Sugar Substitute.—By JOHN MICHELS.—Practical trials of saccharine.—Its advantages and disadvantages..... 10454

II. CIVIL ENGINEERING.—The Corinth (Greece) Ship Canal.—Present aspect of the canal.—Its important influence on railroading and general industries, and on the building interest in the ancient city of Corinth..... 10442

III. DENTISTRY.—Aluminum Bases.—Aluminum as a base for artificial teeth and dentures.—How it is to be manipulated.—3 illustrations..... 10454

IV. ELECTRICITY.—Sir William Thomson's Composite Electric Balance.—By THOMAS GRAY, B.Sc.—Full description of the new balance available as volt-, ampere-, or wattmeter.—1 illustration.. 10445

V. FINE ARTS.—Frog Hunting.—(From a painting by H. Biedermann-Arendts.)—1 illustration..... 10450

VI. MECHANICAL ENGINEERING.—Method of Inserting and Securing Crank Pins.—A plan for using removable crank pins originally devised for carrying out an experiment.—Possible practical applications.—1 illustration..... 10442

VII. MINING.—Mica Mining in North Carolina.—By WM. B. PHILLIPS.—The history of the North Carolina mica mines.—The best localities.—Geological position of the deposits..... 10449

VIII. MISCELLANEOUS.—A New Jersey Pine Forest.—The Lakewood pine grove and the suggestion it offers for the utilization of barren lands..... 10450
Outinian Society.—An old time American society for discussion of general topics and for lectures, founded in 1818, and including Bishop Berkeley among its members..... 10449

IX. NAVAL ENGINEERING.—H. M. S. Victoria.—Launch of a new first class ship of war for the British navy.—Her armament, horse power, and speed as developed on trial trip.—1 illustration..... 10439
Naval Architecture in the Glasgow Exhibition.—Typical vessels shown in model, described, and shown in elevation and deck plans.—9 illustrations..... 10440

X. OBITUARY.—Professor Wroblewski.—Death of the professor of experimental physics at the University of Cracow..... 10453

XI. ORDNANCE AND FORTIFICATION.—Forged Cast Steel Projectiles.—Trial of English steel projectiles against armor plate, condition of projectiles after penetrating.—1 illustration..... 10441
Hydrostatic Disappearing Turret.—The Souriau turret as elaborated by the great Creusot Works of Messrs. Schneider & Co., details of construction and working.—1 illustration..... 10441

XII. PHYSICS.—Experiments with Soap Bubbles.—Mr. C. V. BOYS celebrated experiments fully described and illustrated.—A most interesting paper.—19 illustrations..... 10452
The Gramophone.—Etching the human voice.—By EMILE BERLINER.—The rival of the phonograph fully described, early investigations in this line of work, and history of the invention.—3 illustrations..... 10446

XIII. SANITATION.—Aeration of Water Supplies by Natural Canals and Low Dams.—An attempt to imitate the natural method of aerating water.—How the process is applied at Little Falls, N. Y.. 10451

XIV. TECHNOLOGY.—Protecting Iron against Corrosion.—By H. HAUPT, Philadelphia.—Details of a successful process, recently developed, for producing an inoxidable coating upon iron..... 10442
The Worrell Sand Drier.—Description and illustration of this improved apparatus now in use for drying sand for glass works.—1 illustration..... 10443
Water Gas as used for Metallurgical Purposes.—The water gas process as developed and improved by German engineers, described in full detail and illustrated.—4 illustrations..... 10443


## THE CELESTIAL WORLD.

### TOTAL ECLIPSE OF THE MOON.

The moon will be totally eclipsed on the 22d and 23d. The times of the phases are as follows:

| | d. | h. | m. | |
|---|---|---|---|---|
| Moon enters penumbra ..... | July 22 | 9 | 55·3 | P.M. |
| Moon enters shadow..... | " 22 | 10 | 54·5 | " |
| Total eclipse begins..... | " 22 | 11 | 53·4 | " |
| Middle of the eclipse..... | " 23 | 0 | 44·6 | A.M. |
| Total eclipse ends..... | " " | 1 | 35·8 | " |
| Moon leaves shadow..... | " " | 2 | 34·6 | " |
| Moon leaves penumbra ..... | " " | 3 | 33·7 | " |

The eclipse will be visible generally throughout North and South America, and in portions of Europe, Africa and the Pacific Ocean. It is a repetition of the eclipse of July 12, 1870. The magnitude of the eclipse is 1.825, the moon's diameter being 1.

The total eclipse of the moon of January 28 will be long remembered by observers who were fortunate enough to behold it under the cloudless sky and in the clear atmosphere that widely prevailed at the time. It was one of the most beautiful eclipses on record, and was especially noteworthy for the red, coppery color that revealed the presence of the eclipsed moon in the sky, when entirely immersed in the earth's dark shadow.

The totally eclipsed moon is plainly visible in the firmament in far the greater number of eclipses, the color of the disk varying from a copper hue to a deep, somber gray. The coloring is explained in this way: The sunlight grazing the earth's atmosphere is refracted into the earth's shadow, and the light on the moon is the result. If the atmosphere be pure and cloudless, the moon will present a reddish, coppery hue. If it be full of clouds and vapor, the moon will present a darker and more somber hue. If the earth had no atmosphere, the moon would be invisible during totality.

There are times, however, when the moon is not seen during totality. They are very rare, occurring at long intervals. Such was the case in the two total eclipses of 1884, the latest ones previous to that of January 28. The first of these eclipses took place on April 10, and was observed on the island of Java; the second took place on October 4, and was observed in Europe. The moon was invisible during totality in both instances.

What, then, made so wide a difference between the aspects of the moon in 1884 and 1888? The vapors and fogs pervading the earth's atmosphere would hardly account for the entire absence of light in the one case, nor would the clearer atmosphere fully account for the unusually brighter coloring in the other case.

An ingenious theory has been devised to solve the problem. The dust and vapor filling the atmosphere after the great eruption of Krakatoa, August 26, 1883, is made to account for the curious results in both eclipses. The disturbance in the atmosphere due to Krakatoa dust was manifest in various ways. It was difficult to find Venus in the day time when at her period of greatest brilliancy. Stars of lesser magnitude were difficult to distinguish even on serene nights. The zodiacal light in the spring of 1884 seemed to have disappeared, while the colored circles around the sun and the superb dawns and twilights of 1883–84 have left an ineffaceable impression on the memory. The eclipses of 1884 took place when the atmosphere was in its most troubled condition. The eclipse of January 28 occurred when the atmosphere had recovered its transparency, and was free to exert its highest refractive power. Hence the contrast in the aspects taken on by the eclipsed moon.

The total eclipse of July 22 and 23 will therefore be observed with intense interest, for it will either strengthen or weaken this theory. The conditions of the eclipse are all that can be desired for observers in this longitude. Totality commences when the moon is almost on the meridian, and continues 1 h. 43 m. The time from the moon's entrance into the shadow until she leaves it is 3 h. 40 m. A good opera glass will greatly aid in the observation.

## MILITARY NOTES.

The French squadron, now gathering at Toulon for the regular summer evolutions, has with it an aerostatic corps charged with work of a wholly novel kind. Captive balloons are to be sent up from the ships to heights of 300 meters—about 1,000 feet—and, the weather permitting, still greater altitudes will be attained. As is customary when such ascensions are made from the land, a topographer will go up with the balloon to make a sketch of the underlying country; with special reference to roads and woods or the position of a supposititious enemy if the country is a hostile one, or if friendly, then to mark off on a regular field map his position with reference to the general topography of the country, giving a careful estimate of his strength as to numbers and situation.

When the experiments are made on the French coasts, severe tests may readily be applied to the topographical work done in the sky, for the French have complete charts of their country, both coast and interior, with every cross road and lane accurately determined and laid down, every hill measured, and indeed the position of every house recorded. The topographer in the balloon, however well he can see, must guess as to the effect of the light and color in the foreshortening of the picture beneath him, and at the amount of refraction.

Just now those who are to operate and work in the marine balloons are at practice at Chalais-Meudon, where an aerostatic station was some time ago established. Referring to this practice, *L'Avenir Militaire* says it is quite remarkable the improvement which a really good topographer will make as his eye gradually adjusts itself to the measurement of a diminishing landscape; his work coming nearer and nearer to the original as laid down on the military chart as his experiments continue, for he is allowed, after descending with his sketch, to compare the apparent with the real by the aid of the military map, thus learning where the inclination to magnify or curtail is most pronounced.

It was promised for the new Lebel (French) repeating rifle that it was humane, either killing outright or disabling, but not torturing with the frightful wounds made by single-firers of large caliber, and indeed, so far as known, the magazine guns as well. Recent experiments, however, have shown that the 8 millimeter Lebel magazine gun is no more humane than that of 11 millimeter caliber.

The experiments were conducted by Captain Jaricot, his men firing into dead bodies and at live animals at distances of 200, 400, 600, 1,000, 1,400, 1,600, and 2,000 meters, and the results as summed up by Dr. Delorme are that the orifice made by the entrance of the 8 millimeter ball is smaller than that of its going out, the same varying from 4 to 6 millimeters, according to the velocity of the bullets—the power of the new steel projectile being greater than that of its predecessor, the bones offering less resistance, and there being consequently less deflection of the bullets. The hope that the bones would have a "clear" fracture, with little of the splintering which is so painful, has not been realized. On the contrary, the bone is torn—"shivered" would, perhaps, more nearly express what Dr. Delorme says in the article he writes on *Chirurgie de Guerre*. And yet he says that the effects of the new rifle, as used at present, are trifling compared to what they will be when the new explosives, melinite, roburite, etc., are used.

The readers of the SCIENTIFIC AMERICAN will readily understand the truth of this by recalling the dreadful scenes witnessed at the arsenal at Belfort, March 10, 1887, which were described in these columns; 17 men were killed on that day by the premature explosion of a melinite shell, the bodies being so mangled as to be in most cases unrecognizable, those parts of the skin remaining being tattooed as if they had been covered with minute particles of powder, with grains exploding the one after the other.

The scheme suggested by the French Society Colombophile is a novel, indeed, an important, one, and it seems rather strange, now we are told how much advantage is likely to result, that it was not thought of before. It consists in sending pigeon messengers from ship to ship, the same being on the broad seas and far apart, or near an enemy's country, and needing re-enforcement. A cote has been established aboard the dispatch boat St. Louis, the consort and constant attendant upon the Couronne, line-of-battle ship and school of gunnery at Salius-d'Hyères.

At its recent departure from Toulon, whither it comes every three weeks to revictual, the St. Louis brought young pigeons, which quickly got accustomed to their floating cote, and to the noise of artillery fire, the St. Louis firing at least 600 shots a week from her great guns. At distances small at first, but finally reaching 200 miles at sea, the pigeons were released with messages, those of the St. Louis going to their home cote on the Couronne, and those in the latter flying to the St. Louis. There have been few mishaps, and, strangest of all, the pigeons do not fear, so far as can be seen, the fire of the great guns, at times arriving when they are in full play, and in the midst of heavy clouds of smoke coming from the burning powder. The idea is to keep up constant intercourse between distant fleets which may be operating against an enemy that may appear in force at any moment, and at any point.

## Meeting of the American Association for the Advancement of Science, for 1888.

The date of August 22, for the meeting of the Association, at Cleveland, has been changed by the local committee to the 15th, on account of another great gathering to take place there that week. The special office and reception rooms of the Association will be at No. 407 Superior Street, next door to the Hollenden, where will be the hotel headquarters. The meetings will be held at the Central High School building, on Wilson Avenue, where will be the offices of the local committee and of the permanent secretary during the week of the meeting.

© 1888 SCIENTIFIC AMERICAN, INC.

### Roland Duer Irving.

Prof. Irving, of the University of Wisconsin, died suddenly of paralysis at Madison, Wis., on the 30th of May. Mr. Irving had won for himself the reputation of one of the world's best geologists by his elaborate memoirs as geologist of Wisconsin, and also of the United States Geological Survey, on the archæan and copper-bearing rocks of Wisconsin and the adjoining regions about Lake Superior, and much was expected of him in the continuation of his labors. He was born in New York on the 27th of April, 1847, and therefore had passed but a few days beyond his forty-first birthday. He graduated in 1869 at the Columbia College School of Mines as a mining engineer, and ten years later the institution conferred on him the title of doctor of philosophy. In 1870 he entered on his duties as professor of geology, mining, and metallurgy in the University of Wisconsin, a position which he held until his death. From 1880 to 1882 he was one of the United States census experts.

The new geological survey of Wisconsin, authorized by the State in 1873, included Prof. Irving among its geologists. He had previously begun his study of the rocks, and in February of 1872 published the first of his papers on the subject that appear in this journal. The results of his further labors in the study of the minerals, rocks, and geology of the State occupy a large part of the several volumes of final reports published between 1877 and 1883; and they all bear the marks of careful, conscientious work by one who was thoroughly prepared for the difficult problems before him. His State work, supplemented by additional investigations in 1882, when he was put in charge of the Lake Superior division of the United States Geological Survey, was the basis of his volume on the copper-bearing rocks of Lake Superior, published by the Survey in 1883, and also of other memoirs on the archæan rocks which were preliminary to a full report that remains unfinished. He had selected assistants for the present season but a few days before his death. His paper on the Huronian, in vol. xxxiv. (1887) of this journal, is, we believe, his last publication.—*Amer. Jour. Science.*

### Richard Trevethick.

HONOR TO THE MEMORY OF A GREAT INVENTOR.

A meeting of the subscribers to the Trevethick memorial was recently held, by permission of the Dean and Chapter of Westminster, in the Jerusalem Chamber, in order that the memorial window which has been placed in Westminster Abbey might be inspected. The Dean of Westminster presided, and among those present were Sir George B. Bruce (President of the Institute of Civil Engineers), Sir Charles Hutton Gregory, Mr. Frederick Trevethick, Mr. Hyde Clark, Mr. E. A. Couper, Mr. Joseph Tomlinson, Mr. T. Price Williams, Mr. C. T. Taite, and Lieutenant-Colonel John Davis (secretary of the memorial committee).

The Dean of Westminster, in opening the proceedings, said that when the subject was first suggested to him he was, like the great majority of the outside public, ignorant of the very great claims which he had since learned Richard Trevethick possessed to be placed among the worthies of England. He was greatly struck with the astonishing inventive fertility of the man and with the remarkable fact that he had anticipated advances in applied science associated with the names of engineers more familiar to the world. He had had very great pleasure in acceding to the request for a memorial window in the Abbey.

Sir George Bruce, after thanking the dean for his kindly interest in the movement, said that the proposal for a memorial to Trevethick originated in a feeling, very general among engineers, that his name ought to be lifted out of the oblivion in which it had lain during the fifty-five years since the great engineer's death. Trevethick had died absolutely penniless, and had been buried by the kindly charity of those who had known him best. The mark of deepest effect which Trevethick had made upon the engineering world was the introduction and application of high-pressure steam. He had begun very early with the idea of applying a pressure of 150 lb. per square inch, a plan which had only very recently been introduced into ocean steamboats. Moreover, Trevethick was undoubtedly the first man to make a locomotive to run on rails or common roads; he invented the dredging machine so much employed in our rivers and harbors; he had made improvements in the form and make of boilers absolutely necessary for bringing to anything like perfection the engineering applicances in the use of steam; and he had invented a thrashing machine. He seemed, in fact, to possess a marvelous instinct which enabled him to foreshadow almost all that was to be done in engineering from his day down to the present; he had, for instance, actually patented the application of the screw instead of paddles for driving steamboats.

Sir Charles Hutton Gregory, who also thanked the dean for his assistance to the movement, said that it was a matter of satisfaction to the committee to find how much the name of Trevethick had been honored by working men.

Mr. Frederick Trevethick, as the only surviving son of Richard Trevethick, thanked the Dean of Westminster, the committee, and the subscribers for their recognition of his father's services to the country. His father, a few days before his death, had written, "The great honor of having been a useful subject can never be taken from me, and that to me exceeds all riches."

The Dean of Westminster then invited those present to inspect the window, which, he said, had been executed with great care, and with the advantage of the Archbishop of Canterbury's advice.

The memorial window is situated in the north aisle of the nave and is the third from the west end, being next to that in memory of Brunel. It consists of two finely proportioned lancets, with a quatre-foil shaped piece of tracery above. In the painted glass eight figures of early Cornish saints are represented, standing in two tiers of canopied niches, the name of each figure being written on a scroll beneath. A third row of niches below has figures of angels holding on scrolls outline drawings of some of Trevethick's inventions—namely, the locomotive which ran on the experimental railway in 1803, the locomotive of 1808, the steam dredger patented in 1803, and a Cornish engine and boiler. A figure of the Archangel Michael is placed in the piece of tracery, and in the canopies at the head of the lights are shields with the arms of the See and Duchy of Cornwall.

The amount of subscriptions at present received is $9,300, and of this sum a balance of about $4,000 remains over the cost of erecting the memorial window. With the balance it is proposed to endow an engineering scholarship in Owens College, Manchester, and also to institute a triennial medal at the Institution of Civil Engineers. To carry out these proposals, however, a further sum of £83 will be required.

### The Trans-Caspian Railway.

The consul of the United States at St. Petersburg, Mr. Lothrop, says:

On the 27th of May, being the anniversary of the coronation of the Emperor, Alexander III., the Trans-Caspian Railway was opened formally to Samarcand with great ceremony—an event of no common importance to Russia, and even to the world. This road is 1,350 versts in length (about 900 miles), and is primarily a military road. It has been built and is controlled and operated by the Ministry of War. At present it is little more than a skeleton road. It is deficient in stations and rolling stock. But the great fact is accomplished. It opens the door into the great field of Central Asia. All things requisite to its efficiency will in time be added unto it. Though a military road, its political, economical, and commercial uses and results will not be inconsiderable. It brings Russia nearer to its coveted cotton fields, from which so much is hoped. It has already set in active motion measures for the restoration of the old magnificent system of irrigation, which has fallen into dilapidation and disease. One of the old irrigating canals is said to have been 100 miles in length. All successful cultivation of this region is dependent on irrigation, and a great increase in the production of cotton seems to be confidently expected. The importation of cotton into Russia in 1887 is said to have been 360,000,000 pounds, costing 96,000,000 rubles, and constituting 30 per cent of the entire imports of the empire. And it is mentioned with great pleasure by the public prints that the production of cotton in Turkestan rose last year to 18,000,000 pounds, being double that of any previous year.

It must not be supposed that the Trans-Caspian Railway is likely to rest at Samarcand. Beyond lie Taschkent, Ferghana, and Semiretch, which the Russian journals describe as the richest provinces in Central Asia, abounding in water, inviting colonization and culture. As these lie in the direct path of the interest and the ambition of Russia, the early extension of the railway may be confidently anticipated.

At the same time the project of the construction of the great continental railway across Siberia to the Pacific is agitated with increased intent. It is said that explorations of the line will be begun this year. It hardly seems probable that the available resources of the empire will permit the rapid prosecution of this gigantic undertaking, but it is a work which is necessary to the security and welfare of the Pacific possessions of Russia. Its construction, therefore, is only a question of time.

M. SCOLA has been trying a variety of experimental stains for the glass of dark-room windows, and has fixed upon the following formula:

| | |
|---|---|
| Water | 100 c. c. |
| Gelatine | 5 grammes. |
| Nitrate of silver | 1 gramme. |

Glass coated with this solution is exposed to light until it assumes a reddish brown tint. It is then washed to eliminate the nitrate of silver. A surface is thus obtained through which the actinic rays do not pass. The coloration may be deepened by increasing the proportion of nitrate of silver up to three or even four grammes. Glass tinted in this way may also be used to shade the dark-room lantern.

### Iron and Steel Production.

The United States and Great Britain produced last year three-fourths of the steel and two-thirds of the iron made and consumed among enlightened nations. The pig iron output was 20,820,771 tons, of which Great Britain produced 7,441,927 tons and the United States 6,417,148 tons, Germany standing third on the list with a trifle more than one-half as much as was produced in the United States. The total increase in iron output over the preceding year was nearly 2,000,000 tons, all the iron-producing nations, except Austro-Hungary, increasing their output. The steel product for 1887 was 8,462,390 tons, an increase of 765,374 tons over the previous year. In steel and steel rail production the United States took the lead, Great Britain coming next, and the combined production of the two countries reaching three-fourths of the total product. The increase in iron and steel production in 1887 over the previous year was marked, but much greater in the United States than elsewhere. The increase in iron output outside of the United States was 8·8 per cent, and in the United States 12·9 per cent. The increased production of foreign steel was 26 per cent and of American steel 31 per cent.—*Phila. Times.*

### The Electric Resistance of Copper at Low Temperatures.

A contribution to this subject has just been made by M. Wroblewski, who undertook to test the truth of Clausius' remark in 1856 that the electric resistance of chemically pure metals should be proportional to their absolute temperature. That is to say, if the temperature of a metal could be reduced to the absolute zero, its resistance would be annihilated and its conductivity increase to infinity.

M. Wroblewski, taking advantage of one of the new methods of producing intense cold, namely, that by means of boiling nitrogen at the temperature of its solidification, wires of copper about 4-100 millimeters in diameter and covered with a double layer of silk were taken; their conductivity being guaranteed by the makers as 98 per cent of that of pure copper. With this wire M. Wroblewski wound small bobbins having a resistance at ordinary temperatures of between 3 and 20 Siemens units. As the bobbin had to be plunged in liquefied gas, M. Wroblewski began his investigation by studying the electric properties of liquid oxygen and nitrogen. He found that these substances ought to be ranked among the most perfect insulators. The resistances of the bobbins were then measured by the Wheatstone-Kirchhoff method at the temperature of boiling water; ordinary temperature; the temperature of melting ice; the temperature of boiling ethylene at atmospheric pressure (— 103 deg. Cent.); the critical temperature of nitrogen (— 146 deg. Cent.); the temperature of boiling nitrogen under atmospheric pressure (— 193 deg. Cent.); and a temperature nearly that of the solidification of nitrogen (— 200 deg. Cent. to — 202 deg. Cent.). The results are embodied in the following table, where $t$ is the temperature, $r$ the resistance in Siemens units, and $a$ the coefficient of variation of resistance between two consecutive temperatures:

| Bobbin I. | | | Bobbin II. | | |
|---|---|---|---|---|---|
| $t$. deg. C. | $r$. | $a$. | $t$. deg. C. | $r$. | $a$. |
| —100 | 5·174 | .... | + 23·75 | 19·251 | |
| — 21·4 | 3·934 | 0·004365 | + 23·75 | 17·559 | 0·004057 |
| ± 21·4 | 3·614 | 0·004136 | —103 | 9·848 | 0·004263 |
| —103 | 2·073 | 0·00414 | —146 | 6·749 | 0·004104 |
| —146 | 1·360 | 0·004588 | —193 | 2·731 | 0·004869 |
| —193 | 0·580 | 0·004592 | —201 | 1·651 | 0·007688 |
| —200 | 0·414 | 0·006562 | | | |

These numbers seem to show that the resistance decreases much more quickly than the absolute temperature of the specimens, and approaches *nil* at a temperature not very far from that obtained by evaporating liquid nitrogen in a vacuum.

### Whistling Speech.

At the last meeting of the Berlin Anthropological Society, Lieutenant Quedenfeldt, a German officer who has lived on Gomero Island, one of the Canary group, described a whistling language which is used by the inhabitants. The language does not consist of any arbitrary series of signals or sounds. It is described as ordinary speech translated into articulate whistling, each syllable having its own appropriate tone. The Gomero uses both fingers and lips when whistling, and Lieutenant Quedenfelt asserts that he can carry on a conversation with a neighbor a mile off, who perfectly understands all he is saying. The practice is confined to Gomero Island, and is quite unknown to the other islands of the archipelago. The adoption of the whistling language is said to be due to the peculiar geographical construction of Gomero Island. It is traversed by numerous gullies and deep ravines, running out in all directions from the central plateau. As they are not bridged they can only be crossed with great difficulty; hence a man living within a stone's throw of another in a straight line has often to go many miles when he wishes to see and speak to his neighbor. This, it is conjectured, led to the adoption of whistling as a useful means of communication, which has gradually assumed the proportions of a true substitute for speech. —*St. James's Gazette.*

© 1888 SCIENTIFIC AMERICAN, INC.

### AN IMPROVED SHIP'S LOG.

A device whereby the distance sailed or steamed by a vessel in a given time will be recorded in knots, and the record will be open to inspection at all times, has been patented by Captain Oscar Kustel, and is illustrated herewith, Fig. 1 showing a vertical central section, and Fig. 2 a side elevation. Its mechanism is contained in a cylindrical casing, to be made fast with a line to the taffrail of a vessel, or extended from the side of the ship by a pole, a line extended from the hook at the lower end into the water carrying a rotator, which turns fast or slow according to the speed of the vessel, communicating motion to the mechanism of the log, as the hook is revolved, through a shaft extending upwardly into the casing. An inverted U-shaped frame is held by a centrally apertured disk in the lower end of the casing, as shown in Fig. 1, the central aperture having an outwardly and upwardly inclined side wall, and an apertured conical wheel revolving upon the face wall of the recess, such wheel having three or more friction rollers upon its inclined sides, adapted to travel on the inclined side wall, as shown also in Fig. 4. The shaft vertically entering the casing at the bottom extends upward centrally through the disk and conical carrying wheel, and has an annular projection with beveled under surface adapted to engage the friction rollers, while above such projection it is provided with a worm, whereby its motion is communicated, through successive gear and pinion wheels, to the different registering wheels indicating the number of revolutions made or the distance sailed. By this construction, when strain is exerted upon the vertical shaft, the annular projection thereof, bearing on the friction rollers, forces them against the inclined wall forming their track in a straight line, or at right angles to their axes, in consequence of which there will be no strain on the pivots or axes of the rollers, and no friction or wear on the heads of the pivots, with a very slight amount of sliding friction. In one side of the casing is an aperture covered by a glass pane, and having a series of rectangular recesses, through which the number of knots sailed, as indicated by the registering wheels, can at any time be read.




KUSTEL'S SHIP'S LOG.

For further particulars with reference to this invention address Captain Oscar Kustel, care of Mr. A. Nelson, corner East and Jackson Streets, San Francisco, Cal.

### A DEVICE FOR STOPPING LEAKS IN VESSELS.

The accompanying illustration represents a device for stopping a bad leak in a vessel which has sustained injuries by collision or otherwise, endangering the vessel's sinking, with the loss of the lives of those on board. It is simple in construction and designed to be always quickly available for immediate use. It consists of a canvas sheet stiffened horizontally with iron bars of such diameter and spaced at such distance apart as the draught and other conditions of the vessel may make most expedient. To each end of the upper stay rod is attached a rope by means of which the device is suspended over the side of the vessel when it is brought into service, and to the middle of the upper stay rod is suspended a hook, in the point of which a rope is also made fast. This hook is adapted to support the rolled-up sheet, the rope, as attached to the point of the hook, to be used for releasing the canvas sheet roll, and permit it to unroll downward and cover the break. When a vessel has a hole stove into her, the leak stop is suspended over the side of the vessel directly above the hole and the side lines are made fast on deck, while the middle line is left slack until the hole is definitely located and the leak stop is properly suspended. Then the middle line is hauled taut and made fast, and the side lines are gently slacked to let all the weight come on the middle line, when the hook will drop out and the canvas sheet unroll down and cover the break, the inflow carrying the sheet against the vessel's side and stopping the leak.



WEIHE'S MARINE LEAK STOP.

This invention has been patented by Mr. Louis Weihe, of Connellsville, Pa.

### AN IMPROVED ELECTRICAL ANNUNCIATOR.

An annunciator which is designed to be simple, inexpensive, and efficient is illustrated herewith, and has been patented by Mr. Hiram S. Downerd, of Zanesville, Ohio. Its face has the usual series of figures or characters, beneath each of which is an aperture, through which projects a spindle carrying an index, this spindle being received in apertures in the rims or heads of an electro-magnet, beyond the winding, the magnet being placed directly behind the figure or character. The spindle is located below and a short distance to one side of the iron core of the magnet, and to its rear end is attached an armature having an obliquely projecting finger on its lower end. To the rear heads of the magnet are attached arms of non-magnetic material, with their ends bent rearwardly to form stops, A B, limiting the motion of the armature, and at the side of each magnet is a vertical bar, arranged to move in guides carrying a finger, C, adapted to engage the obliquely projecting finger on the lower end of the armature. The annunciator has as many magnets and associated parts as there are figures or characters upon its face, and for each vertical row of magnets there will be a bar with fingers for engaging each armature, these bars being all connected together, if desired to be moved simultaneously. When a current is sent through the magnet, its magnetized core attracts the armature, causing it to leave its stop, A, and move forward past the center of gravity, dropping, when the core becomes demagnetized by the breaking of the circuit, upon the stop, B, as shown in dotted lines. The armature in dropping turns the spindle, carrying the index through a quarter of a revolution, raising the index to a vertical position in front of the figure or character on the face of the annunciator. To return the armature and the index to the point of starting, the arm, D, projecting through the front of the annunciator, is pushed down, thereby drawing down the vertical bar and bringing the finger, C, into engagement with the obliquely projecting finger on the lower end of the armature, thus throwing the armature over against the stop, A, where it remains by its own gravity.




DOWNERD'S ELECTRICAL ANNUNCIATOR.

HOW SCIENCE ADVANCES.—"He who wishes to keep abreast with the march of science today must leave the college and go to the workshop, and into the dark corners of private laboratories, for investigators rarely have time to write, so that text books are years behind the science itself."—*Prof. Elisha Gray.*

### AN IMPROVED CAN OPENER.

A simple and compact device, whereby a round or square preserving can may be neatly and quickly opened, and so as to leave only a slight margin around the opened top of the can, has been patented by Mr. Jared Blakeslee, of Story City, Iowa, and is illustrated herewith, Fig. 1 showing the device with both a round and a square can in position for operating upon, while Fig. 2 exhibits it in cross sectional elevation. The base has a front round portion for round cans and a rear rectangular portion for straight-sided cans, there being a fixed standard with a vertical slot forming guides in which slides a bar or carrier, on the front of which is fixed a stepped block with concave vertical face, to which may be readily attached a curved and pointed knife or cutter. To the rear of the carrier is also fixed a stepped and straight-faced block for the attachment of a flat-pointed cutter, adapted for use in opening straight-sided cans. A transverse handled lever is pivoted on one of two fixed studs at one side of the carrier guides, and a slot in this lever engages a pin projecting from the face of the carrier, this arrangement giving opportunity for considerable range for the cutters for operating upon cans of varying height, which, when placed upon the proper seat of the base, can be readily cut open as closely to the side as desired by properly working the lever.




BLAKESLEE'S CAN OPENER.

### A CLAMP FOR HOLDING COVERS ON FRUIT CANS.

A device to be employed in putting up fruit in cans, having clamps for holding the covers in place until the wax used in sealing has cooled and hardened, and a scale for weighing the fruit and sugar to be put up, is illustrated herewith, and has been patented by Mrs. Mary J. Hamlin, of Bartramville, Ohio. It consists of an upright standard, with a suitable base, which can be easily set up by screws in the base in any convenient place, the upper end of the standard having a head in which is pivoted a weighing scale, while upon the standard is formed a screw thread on which are mounted any number of lateral arms, which may be raised or lowered upon the upright by turning them about on the screw thread. The outer ends of the arms have set screws to be screwed down against the covers of the cans, which, as fast as they are filled with hot fruit, the covers put on, and the wax applied, are placed under the outer ends of these lowered arms, and the screws tightened against the covers, thereby excluding air and holding the covers in place until the wax has hardened. The set screws in the arms are of different lengths to allow for the different heights of the arms, whereby they may be used upon a number of cans set around the central standard.



HAMLIN'S CLAMP FOR FRUIT CANS.

© 1888 SCIENTIFIC AMERICAN, INC.

### AN IMPROVED CAR COUPLING.

A coupling which is designed to allow the cars to be coupled or uncoupled from either the side or the top of the car, and also to permit of the automatic uncoupling of cars for shunting them about the yard, etc., has been patented by Mr. Herbert S. McKague, and is illustrated herewith, Fig. 2 showing a longitudinal vertical section, and Fig. 3 representing the coupling link. The draw-




McKAGUE'S CAR COUPLING.

head is fitted to slide upon plates, and between beams fixed to the car frame, the plates also supporting buffer plates between which springs are held behind the drawhead. There is a large interior cavity or socket in the drawhead, more than deep enough to allow the coupling link to pass for its entire length into the socket, at each side of which is a flange fixed on the drawhead walls, a little distance from the floor of the socket, making grooves or ways adapted for the travel of a fixed cross bar on the rear end of the coupling link. At the forward ends of these grooves are shoulders, behind lugs or lateral projections having outer faces downwardly inclined to the sloping front face of the drawhead, to which is held a hook or horn, rounded over at its front face, up which the end of a coupling link held by an opposing car may ride, to drop behind the horn for coupling cars. When the link is pushed back far enough in the drawhead socket, the opposite ends of its cross bar will fall from and past the inner ends of the opposite flanges, and as the link is drawn forward the cross bar will ride along the ways until it bears on the shoulders at the forward ends of the ways to take the draught strain of hauling the cars. To lift the outer end of the link, for it to enter an opposing drawhead, and to allow the link to be forced clear back in the drawhead, the link is connected to a chain or cord passed through a slot at the top of the drawhead, and attached to the outer end of an arm fixed on a rock shaft journaled on the car body, which can be operated from either the top or side of the car. A spring is interposed in the connection leading to the operating lever at the top of the car, and also around one end of the rock shaft, whereby, in its operation by the handle at the side or from the top, it may be put under sufficient tension to facilitate the automatic making of a flying switch, the link then only being raised by the rock shaft, through its fixed arm and chain or cord connection, when the draught strain of the moving cars is relaxed.

For further particulars with reference to this invention address Mr. Herbert S. McKague, care of T. C. Hipple, Lock Haven, Pa.

### A DEVICE FOR HOLDING BED CLOTHES IN POSITION.

A holder adapted for convenient attachment to the footboard of a bedstead, so that when the bed is made the clothes will be effectually retained in position, and not be liable to be accidentally thrown off by the occupant, is illustrated herewith, and has been patented by Mr. G. Osgood Andrews, of No. 443 Greenwich Street, New York City. A plate is attached to the inner face of the footboard, near each end, in which a vertically swinging spring-held latch bar is pivoted, and longitudinally upon each plate is secured one member of an essentially U-shaped spring, which is bent outwardly and upwardly to support the latch when in horizontal position. The other members of the springs extend upward beyond the plates, being attached to the ends of a clamping bar extending along the footboard, and provided with corrugated rubber upon its outer or contact side, which prevents the wear of the bed clothes from friction and also serves to retain them more firmly in position on the bed. The clamp bar has a central loop or hand grip, and a cord from each latch is passed through an eye or staple under the cap strip of the footboard. In operation, the mattress being in position, and the sheets, blankets, etc., having been placed so as to leave about four inches of covering at the bottom in excess of the length of the mattress, the clamp bar is pulled forward by its loop handle until the latches are in horizontal position, as shown in the sectional view. The covers are then placed in the space between the footboard and the clamp bar, the latter being then pushed forward slightly to relieve the latches, while with the other hand the cord is pulled to raise the latches from a horizontal position, when the springs act to force the bar in contact with the clothes, and securely hold them between the clamping bar and the footboard, the bed spread covering all and rendering the holder invisible.



ANDREWS' BED CLOTHES HOLDER.

### A REMOVABLE HANDLE FOR CROSS-CUT SAWS.

An improved removable handle attachment for cross-cut saws, which is easily applied and will not bend or break the saw, is illustrated herewith, Fig. 2 showing the attachment in vertical section. The saw blade holder is preferably made in one piece, with a transverse slot, and with a tapering socket portion to receive a wooden handle. It has at the bottom a forward curved or inclined portion, vertically slotted nearly down to its point at right angles to the transverse slot, while the forward portion of the blade holder is also vertically slotted in line therewith. The bottom portion of the transverse slot has an enlarged circular opening to receive a wedging bolt adapted to slide in the transverse slot behind the saw, this circular opening having a projection of the size of a slot in one of the heads of the wedging bolt, whereby the latter may be entered to position. The handle socket has a screw-threaded portion in which is received a screw-threaded stop, its head having slots adapted to engage the upper edge of the saw blade, and the lower edge of the saw blade is notched to fit over the lower end of the inclined portion at the bottom of the attachment within the vertical slot. To secure the handle to the saw, the wedging piece or bolt is pushed to the upper end of the transverse slot, as shown in Fig. 1, when the saw blade is entered in the slot at right angles to the transverse slot, and the handle brought over until the upper edge of the blade rests in one of the slots in the head of the stop screwed into the handle socket. The wedging piece or bolt is then pushed down behind the saw blade, forcing its upper edge firmly against the stop in the handle socket. The stop in the handle is adjustable in its socket to adapt it to saw blades of different sizes.




BLEGEN'S SAW HANDLE ATTACHMENT.

This invention has been patented by Mr. Lars T. Blegen, of Martell, Pierce County, Wis.

### The Coming Naval Revolution.

The new 6 inch gun, throwing a 100 pound projectile and penetrating 13 inches of plating at 1,000 yards, is a gun of sufficient power to deal with almost anything built or building. It may fail to penetrate the strong patch, but it may knock any other part of the ship, and most of the men, to pieces. Mounted on the broadside, under armor, in a small port pierced in a turret which the gun itself rotates, training 120 degrees and firing eight rounds a minute, with a crew of three or four men only, and weighing but five or six tons, those we quote announce in their faces the death of the turret and the barbette.—*Broad Arrow.*

### AN IMPROVED TOBACCO PIPE.

A pipe having a chamber to receive the moisture and oil precipitated in smoking, and in which a cigar holder may be substituted for the bowl, while it is so constructed that the moisture chamber may be




ROESLING'S TOBACCO PIPE.

cleansed without removing the stem, and the moisture will in no case re-enter the bowl or pass up the stem to the smoker's mouth, is illustrated herewith, and forms the subject of two patents issued to Mr. Frederich Roesling, of No. 398 North Perry Street, Cleveland, Ohio. The shank of the pipe is internally threaded at one end to receive the stem, an enlarged smoke chamber being immediately in advance of the stem opening. An upper smoke flue, leading to the smoke chamber from an aperture in the bottom of the bowl, has an enlarged portion immediately beneath the bowl, and the bottom portion of the smoke chamber opens by a narrow passage, as shown in Fig. 1, to a downward sloping reservoir, for the reception of moisture or nicotine, and closed on its outer end by a screw plug. In the form of pipe shown in Fig. 3 the reservoir is placed at a different angle, but in both cases any liquid therein is prevented from entering the stem by the shoulder thereof projecting into the smoke chamber, which is large enough to allow of the passage of moisture, etc., to the reservoir, without interfering with the free smoking of the pipe. The bowl, chamber, stem, and mouth-piece may readily be separately cleansed when desired, although in ordinary use it will be sufficient to simply remove the plug at the bottom of the reservoir and blow out the moisture.

### AN IMPROVED DRILLING TOOL.

A simple and efficient tool, adapted for use on a lathe and in other ways, and which, while drilling a hole, will at the same time serve as a reamer to smoothly finish the hole, has been patented by Mr. Alexander Benzie, and is illustrated herewith. Figs. 1 and 2 show face and edge views of the tool, the working body being preferably milled to a semi-cylindrical form in cross section, to form two diametrically opposite and parallel longitudinal cutting edges, terminating at the outer ends with end cutting edges. The depressed surface between the longitudinal cutting edges may be concave or convex, instead of flat, the parallel reaming edges insuring a straight course for the tool, through which the drillings will pass freely, while the tool, if broken in boring, will loosen itself in the hole and can be readily removed therefrom.

For further particulars relative to this invention address Mr. Alexander Benzie, care of M. F. Kerrigan, No. 35 Willoughby Street, Brooklyn, N. Y.




BENZIE'S DRILLING TOOL.

© 1888 SCIENTIFIC AMERICAN, INC.

### COREA BY NATIVE ARTISTS.

Mr. O. T. Mason, in his description of scenes in Corea, which the engravings are intended to represent, says that the testimony of recent explorers in Corea is to the effect that we have there a human exemplification of the survival of whole genera of industries and customs, while in surrounding regions these have been swept away or transformed. Half a dozen charming books on Corea, notably those of Griffis and Lowell, have portrayed portions of the inner life of a land hitherto closed to our gaze.

Ensign Bernadou, U. S. N., some time ago sent to the National Museum a small, but wisely chosen, collection of art products to illustrate social and industrial life in Corea. Among his specimens is a series of old screens painted in oil on silk, and depicting the paying of tribute by surrounding nations to the Emperor of China. An outer court is filled with attendants, beasts of burden, palanquins, and gifts in endless variety from every part of eastern Asia. Coreans, of course, hold a prominent place. A long procession of ambassadors from these various countries marches through massive gateways, along narrow courts, and over elevated bridges to the throne. There sit the reigning sovereign and his family, guarded by soldiers and attended by nobles. In front of the throne kneel the tribute bearers with their gifts. The faces, costumes, and postures are accurately drawn, but the perspective is thoroughly Chinese in the method of taking advantage of the whole space.

This work of art introduces us to the high life of Corea; but Ensign Bernadou also had the good fortune to obtain nearly a hundred old water color sketches by native artists, portraying industrial life and natural scenery. Eight of these paintings are presented in the accompanying plates. They are rather studies in real life than finished paintings, the latter usually partaking of the grotesqueness characteristic of both Chinese and Japanese.

*Corean Women Washing Clothes* (Fig. 1).—Women are not seen abroad, says Mr. Lowell, excepting servants at the wells and washerwomen. In Corea garments are taken apart to be washed, both the cleansing and the subsequent mangling being effected by means of clubs. When the garment is restored, the seams are pressed close with a very narrow smoothing iron.

*House Builders at Work* (Fig. 2).—Mr. Lowell also describes minutely the work of the joiner and the tiler. Hod carriers are unknown, and unnecessary, because the attendant can easily throw his tiles to the workman, while the balls of mud are passed up in netting. The "chalk line" is blackened with ink. Plane, saw, square, and adz are of the most primitive type. The presence of "the all-seeing eye" also seems necessary.




COREA BY NATIVE ARTISTS.

© 1888 SCIENTIFIC AMERICAN, INC.

*Spinning and Weaving* (Fig. 3).—The textile practices of Corea exhibit the most primitive types of Chinese weaving. The loom for matting is very rude, although the work is excellent. The warp is held in place by a stone tied to the end of each thread. Half of these rest on one side and half on the other side of the upper beam. After the insertion of a weft straw, each of these stones is shifted to the opposite side.

*Shoeing a Refractory Horse* (Fig. 4).—The blacksmiths and other metal workers of Corea are quite clever. Some of their silver and copper inlaying done on jewelry boxes and furniture contrasts favorably with similar work by their neighbors. The bellows consists of a square box, in which a plunger of wood, packed with paper, passes up and down.

*A Lesson in Archery* (Fig. 5).—Archery is still a favorite amusement among the Coreans, and their soldiers are obliged to compete in yearly practice for prizes. Men of straw are set up in boats as marks. Great care is bestowed both on bows and arrows, and the junior members of the corps are carefully instructed in the precedents of practice.

*Bonzes Selling Charms* (Fig. 6).—Mr. Lowell characterizes Corea as a land devoid of religion, Confucianism swaying the upper classes and old superstitions the lower. Sorcerers and fortune tellers sell their charms to men and women, often parading them in public and announcing their presence with rude music. Mr. Griffis' "man of straw" plays an important part, even now being sold and kicked to pieces as a scapegoat for the man's former self. In the drawing of the sorcerer is exhibited the quaint custom among Corean women of wearing on the top of the head a garment which they may draw over the face on the appearance of a man.

*A Wedding Procession* (Fig. 7).—In the wedding procession we see the lantern men preceding; the bearer of a wild duck or goose or a model, symbol of domestic felicity; the happy bridegroom, seated on a horse led by a man and attended by another; last of all, the bride, attended by a young boy. Her garment, ready to cover her face on meeting a man, is characteristic, as well as the court dress and robe of the groom.

*Peddlers on the Road* (Fig. 8).—Peddlers are common throughout Corea. In our sketch are represented the methods of carrying loads and children, and the costume, hat, and shoes of the lower classes.

Each one of the paintings is as graphic and instructive as those presented. It is very difficult to impress upon the mind of ordinary travelers that it is just the information conveyed in such pictures that the anthropologists need. To write the life history of our practical arts, it is absolutely necessary to understand the minutiæ of industry in every stage.

It is clear that outside of the charm of the unknown, Corea is a distinctively interesting region. The views which we give herewith, and for the use of which we are indebted to the *Swiss Cross*, illustrate in some degree the quaintness of her people and their characteristic ways.

[THE SCIENTIST].

## Bee Culture.

In the oldest writings mention is made of the bee, honey, and the honey comb, and a land flowing with milk and honey. From this we infer that the common honey bee has been known since the dawn of civilization, and that it is of Asiatic origin.

This insect has been the theme of many writers. Volumes have been and are being published, and there are journals devoted wholly to this subject.

Bee culture possesses a fascination peculiar to itself. The study of any other species of the animal kingdom cannot equal it. This is due, in a measure, to the many superstitions with which it was regarded. To-day, even, there are many people who believe that when a bee owner dies, some member of the family must communicate this intelligence to the bees by rapping on the hive. You will be interested in reading a poem by Whittier, entitled "Telling the Bees."

In the 18th century, Huber, a Swiss naturalist, who became blind at the age of fifteen, published many articles on the natural history of the honey bee. These writings are the first to tell the truth, and are quite remarkable, considering the way in which the experiments and observations were made.

If a prosperous colony be examined in June, there will be found three kinds of bees, viz., the queen, the workers, and the drones, also three kinds of cells. Two of these will be horizontal and hexagonal, and will differ in size only. The smaller is the worker cell, the larger the drone cell. The third cell is much larger than the others, and resembles an inverted cone with the opening at the apex. The different cells will be found to contain various substances—such as honey, pollen, eggs, and immature bees.

The queen is rightly named, for without her no colony can exist but for a short time. She is longer and more slender than the others, and is armed with a sting. The abdomen is quite tapering, and the wings short. She is the only perfect female in the hive, and during the height of the breeding season lays from two to three thousand eggs per day. This seems an exaggeration, but it does not equal the fecundity of the female of the white ant, which lays at the rate of sixty per minute. The queen has it in her power to lay drone or worker eggs. She will deposit in the worker cells the right eggs, and as it happens many times, the drone cells border these, but no mistake is made, for on examination no worker is found in a drone cell, but drones may be found in worker cells as was intended. This takes place when the apiarist removes all the drone cone, which gives no other place for the drone eggs. About ten days before swarming, eggs are laid in the queen cells, so that when the swarm issues a new ruler will be ready to take steps to carry on the work of the old. This work consists mainly of laying the eggs. The queen is much respected by the workers, a body guard of which encircles her. The food consists mostly of honey which is taken from the proboscides of the workers.

The worker bee, incorrectly called the neuter, is a female with ovaries imperfectly developed. It is smaller than the queen or drone, but has longer wings, is armed with a sting which it is ever ready to use in defense. The instrument is less than one-eighth of an inch in length, is hollow, and has two sacks at the base that contain poison. The sting is left in the wound, and the poisonous sacks and a portion of the intestines adhere to it. If the sting is removed from the wound immediately, little harm will result. Otherwise the muscles of the sacks contract and force all the poison into the system. When a bee loses its sting, it soon dies. Hornets, wasps, etc., do not have a barbed sting. They retain it, and can sting many times in a moment. Does it seem that the worker would be as ready to act on the defense if it knew what would be the result? The queen is quite different in this respect. She cannot be induced to sting except in mortal combat with another queen. The bystander will not interfere, and after a short conflict one falls a victim and the other becomes supreme ruler.

The hinder legs of the worker contain a spoon-shaped cavity or basket in which the pollen from the flowers is gathered, and a sticky substance called bee glue.

The worker is furnished with a tongue or proboscis, with which it takes the nectar from the flowers. Honey is gathered, not made. The honey is conveyed to the honey bag or first stomach. This receptacle is about the size of a pea, and is furnished with muscles which enable the bee to compress it and force the contents into the cell. When honey and pollen are abundant, a load of each is gathered. Less than twenty minutes are consumed in doing this. When gathering pollen but one kind of flowers is visited, else there would be considerable confusion in the vegetable world. During the busy season the worker has no rest, and, of course, wears out quite fast. At this time few live to be more than six weeks old. At other times they may live five months. An old bee can be distinguished from a young one by the ragged edges of the wings. In the abdomen of the worker are pouches or sacks for the secretion of wax, which is the fat of the bee. This can be formed or not, as occasion requires.

The drones are the male bees. They are longer and stouter than either the queen or workers, but their bodies are not so long as that of the queen. They are not armed with a sting and have no suitable proboscis for gathering honey from the flowers. There are no baskets on their thighs for holding bee bread, and no pouches on their abdomens for secreting wax. Many allusions are made about the drone because he is such a lazy fellow. He does what nature intended him to do, and that is all—to impregnate the young queens. Soon after this is accomplished the workers destroy them. This is done by biting and stinging. In this work the sting is not left in the wound.

The comb is made of wax, and consists of hexagonal cells of two sizes. The smaller are the worker, the larger, the drone cells. It has been found that no other arrangement will give an equal strength and volume with the same material.

The more we read and reflect on such subjects, the more we find

"Tongues in trees, books in running brooks,
Sermons in 'bees,' and 'God' in everything."

*George H. Hastings.*

## When to Cut Hay.

The farmer seems to think that it is all very well for men to write about hay with the bloom on and an odor like southern breezes over a bed of violets, but when it comes to feeding the old cow he wants to see her chew on something that will keep her busy and will last awhile. The green-tinted hay stack melts before a herd of cows like a snow bank in a hot sun, while the dry old yellow article remains a monument of the hay field until the green grass makes its appearance once more. To be sure, the cows are somewhat thin, perhaps, and no profit has been made out of the cows in milk, but there has been no worry about buying ground feed or fodder corn to help carry the herd through the winter. Some men can suck consolation out of mighty dry substances.—*American Dairyman.*

## Breaking in a Naval Cadet.

Within a few days the cadets shake easily into their places, and by going over the masthead every morning, sending up and down the light spars and being ordered to get a pull here and a pull there and a long pull altogether everywhere during the best part of their waking hours, they soon acquire a nautical air and a fairly good grip upon the strange surroundings. Two or three days later the Constellation drops down the Annapolis Roads, stands into Chesapeake Bay, and the long looked for cruise begins. Practical work commences at once, and if the winds be unfavorable—and they are usually—the ship beats down the bay in the daytime and anchors at sunset. Here the new cadet sees the envied senior class man in charge of the deck make and take in sail, tack, wear, boxhaul, and chapel ship, sees him occasionally miss stays and box her off, heave to, get casts of the deep sea lead, shift sails and spars, reef and shake out reefs, and bring the ship to an anchor. All this time he is doing yeoman's service himself, his hands get horny and hard, his white working clothes are tarry, and he is so used to "stamping and going it" that when night comes he is glad to turn in early and leave the hardships of anchor watch to those who have enjoyed the triumphs of the quarter deck.

After Hampton Roads are reached the vessel lies at anchor for a week or more, but this is a busy season, and all day long there are great gun company, pistol or small arm drills, fire quarters, boats armed and equipped, or that stirring exercise when the crew and cadets are called to "abandon ship." This drill is usually executed without previous warning, exactly as it might be needed in any sudden emergency, as in a collision or danger of foundering on the high sea; but within a moment after the order rings out every one is at his station, some lower the boats, others stand sentry over the falls, so no unauthorized or panic-stricken person may enter without orders, the majority pass up provisions and water, cooking utensils, arms, ammunition, and nautical instruments, there is heard everywhere the rush of feet, the whimper of boat falls as the davits creak and complain with the strain and the weight of the crews lowering themselves by stopper or halyards, from every gun port willing hands pass stores into the cutters, and when ready each reports its name and number. In less than five minutes, if the discipline be good, the crew is embarked in cutters, whale boats, launches, gig, and dingey, all submerged almost to their gunwales, and the ship is abandoned officially.—*Lieut. Kelley, in Harper's Magazine for July.*

## Flour Yields.

We have before us a half dozen daily reports, taken at random from the files of a merchant mill, one of which we reproduce, to show the form in which such a record may be kept. It is as follows:

DAILY RECORD, MAY 1, 1888.

Twenty-four hours' run.

| | | | | |
|---|---|---|---|---|
| 846 | barrels | Patent | 66·82 | per cent. |
| 342 | " | Bakers' | 27·01 | " " |
| 41 | " | Low Grade | 3·24 | " " |
| 37 | " | Red Dog | 2·93 | " " |
| 1,266 | " | Total | 100 | " " |
| 46,400 | pounds | bran or | 36·65 | pounds per barrel. |
| 29,200 | " | middlings, or | 23·06 | " " |
| 75,600 | " | Total, or | 59·71 | " " |

5,501 bushels wheat used.
4 bushels, 20¾ pounds yield per barrel.
31,019 pounds of coal used, or 24½ pounds per barrel.

While a record in precisely this form might not suit the conditions of every mill, there is no question but it would pay every merchant mill, no matter whether large or small, to keep a regular daily record of similar character. Where the wheat supply of the mill is drawn from various sources and the grades and quality differ, the record could be made more complete by noting on it not only the amount of wheat ground, but also the amount and character of the grades of wheat used each day. In the half dozen reports at hand, the yield varies from 4·18 to 4·22, which is explained by the varying quality of the wheat ground. A set of reports of this character, made out on cards and filed away, or entered in a book kept for the purpose, would not add any to the expense of the mill's bookkeeping and would be most valuable for reference and as a constant guide by which to check up the commercial operation of the mill.

No matter upon what system the mill is operated, whether long or short, a difference of a few pounds in the yield per barrel will work either for or against the profit balance with steady regularity.

It may seem needless to figure up the record every day, but if the miller knows exactly what his mill did yesterday, he will be better able to make it do as good work to-day, and more certain of making it do good work to-morrow.

The mill from which the report is received is probably doing as well as any mill which is running under similar conditions, and it is safe to conclude that the average mill does not get much, if any, over 70 per cent of flour out of the wheat it grinds.—*Milling Engineer.*

© 1888 SCIENTIFIC AMERICAN, INC.

### Deceptive Senses.

The senses are subject to illusions in proportion to the remoteness of the information that they give from the immediate necessities of the organism. Touch, the most immediate and least inferential of the senses, is least subject to illusions, while sight is so very much so that the blind often say they have an advantage over the seeing in being free from visual illusions. The illusions of bodily motion are much nearer to those of touch than to those of sight, and yet they can under certain conditions be induced through visual impressions. Of this the writer has recently had two interesting examples. He was standing upon the floor of a railroad depot, the boards of which were laid with a considerable open space between them, and the shadow of an electric light was moving up and down by the swinging of the light in the wind. Looking at the floor, it seemed as though the shadow were stationary, and the floor boards moving. From this it followed that the person on it was moving too, and the writer distinctly felt the swinging sensation, in fact his attention was called to the phenomenon by this feeling of motion. The other observation was as follows: While riding in the cars and looking out of the window, the trees and all are seen to move in the opposite direction. If, now, one looks in a mirror so situated that it reflects the passing landscape, which, however, must not be visible except in the mirror, one has the illusion of moving in the opposite to the real direction of motion, owing to the reversal of the image in the glass. In both these cases an immediate bodily sensation is induced by a more or less unconscious inference through visual sensations.—*American Analyst.*

### Oil Rockets.

An improved method of distributing oil on the waters consists of a rocket to which is attached a cylinder filled with oil. It is said that the rocket can be fired with accuracy from the ship, and that, when it explodes, the oil is scattered just where it is wanted. Several interesting experiments have recently been made between Bremen and New York. In one the rocket was fired to a distance of 1,500 feet and less distances. By the explosion of five rockets at a distance of from 1,200 to 1,500 feet from the ship, a space of 1,500 to 2,000 square feet of water was covered with oil, and the waves were at once smoothed. The rocket was fired 900 feet against a gale. The importance of the invention to deep-water sailors consists in the certainty of explosion of the rocket at a sufficient distance to leave the vessel in calm water during a gale. The invention is said to have been purchased by the North German Lloyd.

### Electrical Street Cars.

The Fourth Avenue street car company, of New York, is about to commence running its cars by means of electrical storage batteries carried under the car seats. The company appointed experts to make calculations as to the ratio of cost, gain, and loss in the three methods of propelling street cars. The following are the results:

| | Electric. | Horse. | Cable. |
|---|---|---|---|
| Cost of cars | 1 | 0·54 | 0·81 |
| Motive power | 1 | 1·45 | 1·06 |
| Construction of roadway | 1 | 0·53 | 2·09 |
| Depreciation and repairs | 1 | 1·47 | 2·04 |
| Operating expenses (including wages) | 1 | 3·38 | 1·71 |
| Totals | 5 | 7·37 | 7·74 |
| Average | 1 | 1·47 | 1·55 |

### THE MANUFACTURE OF FISHING NETS.

The two extremes of the manufacture of fishing nets are represented, on the one hand, by the net of primitive peoples, composed of branches of very leafy trees connected by vines, and, on the other, by nets made mechanically.

Up to the present, the machine-made net, however, has not replaced the hand-made one. This latter manufacture is justified by the fact that it occupies the wives and children of sailors, affords them very useful though not very remunerative work, and gives a product which, up to the present, has not been equaled by mechanical manufacture.

Nevertheless, the ever increasing requirements of maritime fishery made it necessary to find a mechanical device that should produce a net exactly identical with that made by hand, and that should direct the meshes in a like manner—conditions indispensable for obtaining great strength and preventing the net from getting out of shape.



IMPROVED MACHINE FOR MAKING FISHING NETS.

This problem, which has been worked upon for over twenty years, and has given material for a certain number of patents that introduced further and further improvements, seems to be finally solved in the frame represented in the accompanying engraving, which is reproduced from a photograph of a model which was operated at the Havre maritime exhibition in 1887.

The Galland and Chaunier frame has the general appearance of the large lace frames, and borrows from the latter its main parts (carriages and comb bars), thus permitting of the setting up of machines for manufacturing nets of very great widths (say of from 500 to 600 meshes), and which have relatively simple motions, and act with great precision. The nets manufactured with this new machine are exactly like those made by hand. All the textiles used in the industries can be worked on it, and meshes of variable sizes can be made, either in a single piece, the entire width of the machine, or in several widths provided with natural selvages. According to the material employed, the frame is capable of producing eight or twelve rows of knots per minute, and it takes but one workman to run it.

The machine consists essentially of the following parts: 1. Of a roller placed at the upper part, and upon which is wound the warp twine. 2. Of a bar provided with small steel tubes, and moving under the roller. 3. Of a bar carrying a series of parallel needles. And 4. Of a bar carrying a series of pieces in the form of a bent finger, moving between the tube and needle bars, and carrying also another bar provided with teeth like those of a saw.

These four bars carry as many tubes, needles, fingers, and teeth as there are warp strings on the roller, and all these pieces are equally spaced upon the bars that carry them. This spacing can be regulated at will, and permits of forming meshes varying from 8 to 50 mm. from knot to knot.

The operation of the parts is as follows: The twine from the roller falls in parallel rows, and is passed respectively into each of the tubes of the tube bar, then runs between the fingers and to the left of that which it is to surround, passes between the needles, and the various lengths join at the last knot made. The tube bar performs its evolution, and in this motion each tube passes first to the right of the finger facing it, then descends, surrounds the needle placed opposite, and returns to its first position by passing to the left of the finger that it has surrounded. The lengths of twine, guided by the tubes, have then formed triangular loops between the fingers and the needles, leaving a single length to the right and two lengths to the left. In measure as this maneuver takes place the roller descends so as to pay out the twine necessary for the formation of the loops. These formed, a series of shuttles, exactly like those of lace frames, and carrying the woof, are set in motion and traverse the loops. At this moment the toothed bar takes the second length which is to the left of the finger and carries it to the right, and the shuttles return and pass into this loop, and again take their first position. The woof has then passed all around the third length of the movable twine.

The finger bar then descends, and, reversing itself, leaves its loops upon the needles and returns to its first position. At the same time the roller has risen again so as to take up the twine that it had paid out for the formation of the loops, and, at the moment that the fingers free the latter, it gives the twine quite a strong tension, so as to tighten the knots on the needles. The needles move back and free the knots, and the rubber-covered rollers between which the twine runs, on revolving a certain amount, cause the line of knots to descend.

The production of a frame like the one just described varies with the width of the net and the nature of the twine used. For a width corresponding to 500 meshes and a mean velocity of ten rows per minute, the theoretical production of ten hours' work would be 3,000,000 meshes. Estimating the time lost in renewing the shuttles, etc., as one-third, a production of 2,000,000 meshes per day may be counted upon.—*La Nature.*

© 1888 SCIENTIFIC AMERICAN, INC.

## REPRODUCTION OF ARTICULATE SPEECH AND OTHER SOUNDS.

(*Continued from first page.*)

cording surface, and perfect accuracy in the same, or centering for the cylinder, is rendered unnecessary. To the diaphragm cell is attached a flexible tube, furnished at its free end with a mouthpiece, into which the words to be recorded are spoken.

The record cylinder consists of paper wound in a peculiar way, to cause it to maintain its cylindrical form, the outer surface of the paper being coated with a specially prepared wax. Below the cylinder is arranged a pan for receiving the fine shreds of wax cut by the stylus from the cylinder in the operation of recording the message. The groove constituting the record is microscopic in size, it being only three thousandths of an inch wide and about two thousandths deep. One hundred and sixty grooves to the inch are cut on the cylinder. The saddle which holds the diaphragm cell is formed of two parts hinged together to facilitate its removal from the support.

Fig. 3.—LONGITUDINAL SECTION OF RECORD CYLINDER.

After the complete record has been made, the cylinder is either removed and placed in another machine, or it is allowed to remain, and the recording diaphragm is replaced by the small reproducing diaphragm shown in Fig. 5. This diaphragm is connected by a thread with a small rounded finger pivoted in the end of the arm which supports the diaphragm, and adapted to engage the groove and indentations made by the stylus of the recording diaphragm.

To the reproducing diaphragm cell is attached a flexible tube, which is branched and provided at its extremities with ear pieces similar to those of a stethoscope. The ear pieces are placed in the ears, as shown in Fig. 1. The rotation of the cylinder containing a message causes vibrations to be set up in the reproducing diaphragm which are similar in character to those of the recording diaphragm which produced the impressions upon the cylinder.

The machine is driven by connection with any power having a fairly uniform speed. In the engravings the machine is represented as being driven by a small electric motor.

The paper cylinders are very light, perfectly portable, and may be transmitted by mail with the same facility as an ordinary letter. The cylinder will fit any graphophone without any adjustment of the instrument.

The graphophone has been in practical use for some time past, carrying on correspondence between New York and Washington, and in receiving dictations in every-day matters of business, the dictations being written out on a type writer by a copyist who listens to the graphophone.

By means of the starting and stopping key, which throws the driving wheel in and out of gear with the recording cylinder, the message can be reproduced sentence by sentence, and reproduction stopped between any two words, or in the middle of a word if desired. This enables the copyist to take from the graphophone as many words as can be retained in mind, and the machine waits while they are being printed on the type writer or written out, as the case may be. Should it be desired to repeat the message, a simple motion of the hand, occupying only a second or two, places the reproducer on any part of the record, and the latter can be repeated a thousand times if desired.



Fig. 4. SECTION OF RECORDING DIAPHRAGM.

Fig. 5. SECTION OF REPRODUCING DIAPHRAGM.

The graphophones in general use are provided with treadle motors, which, acting through a very sensitive regulator or governor, gives to the record cylinder a perfectly uniform motion of rotation, and as all machines are regulated to run at exactly the same speed, a record made on one machine can be reproduced correctly on any other.

## THE NATIONAL SYSTEM OF PURIFYING WATER BY FILTRATION, PRECIPITATION, AND AERATION.

A new system for the filtration and aeration of water for the supply of cities and towns, and whereby also water may be readily and thoroughly purified for manufacturing purposes, at a comparatively small cost, is being introduced by the National Water Purifying Company, of No. 145 Broadway, New York City. The accompanying illustration represents the plant furnished by the company for purifying the water supply of the city of Chattanooga, Tenn., the system having also been adopted for public purposes at Champaign, Ill., Lawrence, Kan., Winnipeg, Man., Kokomo, Ind., Exeter, N. H., and Hackensack and Hoboken, N. J., and by numerous manufactories in all sections.

The water enters the filter at the top, under pressure, and passes down through a bed of fine sharp sea sand, or coke and sand mixed, to the outlet valves at the bottom, which are so arranged as to prevent the escape of any of the filtering material. A precipitating device, which can be opened or closed at will, is arranged in the water space above the filtering material, and near the inlet pipe, to furnish a certain amount of alum or other chemical to the inflowing water, where such addition is needed for the precipitation of sewage, vegetable stain, etc., this precipitate being deposited with the impurities at the top of the filter bed, and thrown out when the filter is washed. To cleanse the filter, a washing pipe, with lateral branches, having perforations on their upper surface, is arranged from ten to twelve inches below the top of the filtering material, and, the inlet pipe having been closed, and a waste pipe near the top at the opposite side opened, a reverse current is sent through the top surface of the filter bed. As it is well known that most of the impurities taken from water by a filter are deposited at or near the top of the filter bed, it is found that, in general practice, five minutes' time will be sufficient, with a strong reverse current, to wash out the impurities that would be taken from the water in five hours, when the water being filtered is quite bad, while it will not be necessary to wash the filter but once a day, unless the water is very muddy and impure. Besides this layer of washing pipes near the top of the filter bed, a similar layer of pipes is arranged in connection with the outlet valves at the bottom, whereby, when it may be deemed necessary, or once in every twenty-four hours, a reverse current may be sent through the bed from the bottom, after first washing the top of the bed, as before, to break up the



FILTER PLANT OF NATIONAL WATER PURIFYING COMPANY AT CHATTANOOGA, TENN.

© 1888 SCIENTIFIC AMERICAN, INC.

passages made by the water in previous filtering. The ability to clean the filter so quickly does away with the necessity, in most cases, of using alum or other chemicals to produce sparkling water, and great economy is effected in the water used for cleansing the filter bed, by thus washing the top part only in ordinary service, there being no loss of head or pressure, or of the filtering material.

We append a report on the National filter plant at Chattanooga, Tenn., which forms the subject of our illustration:

To W. S. KUHN, General Manager, American Water Works and Guarantee Co., Pittsburg, Pa.

DEAR SIR: Having made a thorough test of the National filter plant, I find as follows:

That it will readily purify three million gallons per day. In fact, the ten No. 17 filters gave four million gallons in twenty-four hours, of Tennessee River water, removing all suspended matter and impurities, and rendering the water clear and bright. In washing the filters they are arranged to wash two at once, doing away with the necessity of operating one set of valves. Each battery of two filters takes but twenty-four minutes in cleaning, or two hours to thoroughly wash the entire plant of ten filters, using a four inch pipe in washing, under 45 lb. pressure, thus making the plant very economical in time and water in cleansing. There is a bed five feet deep of Long Island sand in each filter. This sand is entirely without crevices, and can be thoroughly cleansed by a reversed current. In washing the filters, the top of the bed, say six to twelve inches, is washed first, as most of the impurities taken from the water in twenty-four hours are lodged on the surface of the sand bed. Four minutes' flow of water will answer for the surface washing; then a reverse current is sent through the bottom of the bed, which breaks it up and throws out all of the finer particles in the lower part of the sand bed. No labor is required in the process of washing, the pressure of the water alone accomplishing, by the reverse current, a thorough cleansing of the sand bed in the filters, the only labor necessary being to open and close the valves in the pipes once each day, which requires no skill.

The citizens of Chattanooga are to be congratulated on the result produced by our National filter plant; and in future they will have as handsome and pure a water supply as New York City, which is conceded to be the best in the world for domestic and manufacturing purposes. And this fact of the purity of our city water supply should lead to an increased interest in our city and a rapid growth in population.

Respectfully submitted,

NISBET WINGFIELD,
*Supt. City Water Co.*

Chattanooga, Tenn., June 25, 1888.

The aeration of the water is accomplished by means of an air compressor, whereby air is forced into the water under a high pressure. The process is simple and inexpensive, and the amount of air forced into the water can be regulated as desired, according to the requirements in each case. This system can be applied to open filter beds, as well as to the closed top pressure filters shown in the illustration, and with a great saving in labor, as the pressure of water in washing the filter beds is far more effective in a very short time than a great amount of manual labor expended according to the old methods.

These filters are regularly made in sizes of a capacity ranging from 5 gallons to 250 gallons per minute, the company furnishing the plant to meet the desired maximum supply, and guaranteeing its capacity, whether for an individual manufacturing establishment or for the water supply of a large city.

### Seasonable Hints for Comfort and Health.

*A Good Disinfectant.*—Dissolve half a drachm of nitrate of lead in a pint of boiling water, then dissolve two drachms of common salt in eight quarts of water. Pour the two mixtures together. After the sediment has settled, the liquid is a saturated solution of chloride of lead. A cloth dipped in it and hung up in a room will purify a fetid atmosphere. It may also be used to pour down a sink, drain, or water closet. This is very cheap, as a pound of nitrate of lead will make several barrelfuls of the disinfectant.

*Damp Cellars.*—If a cellar has a damp smell and cannot be thoroughly ventilated, a few trays of charcoal set around on the floor, shelves, and ledges will make the air pure and sweet. If a large basketful of charcoal be placed in a damp cellar where milk is kept, there will be no danger of its becoming tainted.

The following, it is said, is an admirable cure for damp cellar walls: Boil 2 ounces of grease with 2 quarts of tar for nearly twenty minutes in an iron vessel, having pounded glass 1 pound, and slaked lime 2 pounds, well dried in an iron pot and sifted through a flour sieve. Add some of the lime to the tar and glass to form a thin paste, only sufficient to cover a square foot at a time about an eighth of an inch thick.

*Keeping Butter.*—A simple mode of keeping butter in warm weather is to invert a large crock of earthenware, or a flower pot, if need be (varying with the size of the vessel containing the butter), over the dish or firkin in which the butter is held. The porousness of the earthenware will keep the butter cool, and all the more so if the pot be wrapped in a wet cloth, with a little water in the dish with the butter. Not the porosity of the earthenware, but the rapid absorption of heat by external evaporation, causes the butter to become hard.

*To Expel Mosquitoes.*—Take of gum camphor a piece about one-third the size of a hen's egg, and evaporate it by placing it in a tin vessel, and holding it over a lamp, taking care that it does not ignite. The smoke will soon fill the room and expel the mosquitoes, and, even though the windows should be left open all night, they will not enter the room as long as the odor remains.

*How to Cool a Cellar.*—A great mistake, says *Medical Classics*, is sometimes made in ventilating cellars and milk houses. The object of ventilation is to keep the cellars cool and dry, but this object often fails of being accomplished by a common mistake, and instead the cellar is made both warm and damp. A cool place should never be ventilated, unless the air admitted is cooler than the air within, or is at least as cool as that, or a very little warmer. The warmer the air, the more moisture it holds in suspension. Necessarily, the cooler the air, the more this moisture is condensed and precipitated. When a cool cellar is aired on a warm day, the entering air being in motion appears cool, but as it fills the cellar, the cooler air with which it becomes mixed chills it, the moisture is condensed, and dew is deposited on the cold walls, and may often be seen running down them in streams. Then the cellar is damp and soon becomes mouldy. To avoid this, the windows should only be opened at night, and late—the last thing before retiring. There is no need to fear that the night air is unhealthful; it is as pure as the air of midday, and is really drier. The cool air enters the apartment during the night and circulates through it. The windows should be closed before sunrise in the morning, and kept closed and shaded through the day. If the air of the cellar is damp, it may be thoroughly dried by placing in it a peck of fresh lime in an open box. A peck of lime will absorb about seven pounds, or more than three quarts, of water, and in this way a cellar or milk room may soon be dried, even in the hottest weather.

### Sterilized Milk as a Food.

In the April number of our esteemed contemporary the *Dietetic Gazette* is an article by Dr. A. Caille upon the mode of preparing sterilized milk for the use of infants. The fact that milk just as it comes from the breast of woman or the udder of the cow is aseptic makes it *a priori* reasonable to believe that aseptic milk is the most natural and healthful form to use. The readiness with which milk becomes impregnated with germs and undergoes fermentation is well known. To rid it entirely of these germs, Dr. Soxhlet, of Munich, has devised a sterilizing apparatus which is easily used, comparatively inexpensive, and has been, we are told, extensively introduced into households at Munich. This apparatus consists essentially of a number of small (five ounce) glass bottles, with rubber and glass stoppers combined. There is a tray for holding these, fitting in a tin pot for boiling the milk. The milk is raised to a boiling point in the small bottles. These are then hermetically closed and kept at 212° F. for twenty minutes, when the milk is sterilized. The process is really, therefore, only one of prolonged boiling under pressure. Dr. Caille made a number of experiments with milk sterilized in Soxhlet's apparatus and with milk boiled in the ordinary way. Results, as stated, were:

1. Milk sterilized in Soxhlet's apparatus, boiled thirty minutes, remained good eighteen days.

2. Milk boiled in small bottles for fifteen minutes; before removing from the boiling water the bottle was closed with a pledget of cotton. This milk remained good five days.

3. Milk boiled in small bottles for fifteen minutes; then taken from the water, and each bottle closed with a tight, non-perforated rubber stopper. This milk remained good five days.

4. Milk boiled in small bottles for fifteen minutes; then taken from the water and each bottle immediately closed with a good quality cork stopper. This milk remained good five days.

5. Milk boiled in a pot, and put into small bottles after cooling, and closed with a cork stopper. Sour after four days.

6. Milk boiled in a pot, and put into small bottles after cooling, and closed with non-perforated rubber stopper. Sour after four days. [This milk was kept in a spare room with temperature ranging from 50° to 70° F.]

7. Milk boiled in a pot in the usual manner, and left standing in an open dish in a room with a temperature of 75° F.: (*a*) ordinary store milk had a distinct sour taste and smell after *eight hours;* (*b*) good "bottle milk" "turned" after fifteen hours.

8. Milk boiled in a pot in the usual manner and placed in the ice box in an open dish: (*a*) ordinary store milk "turned" after eighteen hours; (*b*) good bottle milk "turned" after twenty-six hours.

Dr. Caille further concludes that:

The boiling of milk for twenty to thirty minutes under slight pressure, in small bottles hermetically closed, is all that is necessary to practically carry out the principle involved in sterilization; *i. e.*, to destroy the germs of fermentation.

The essential materials are small bottles with Soxhlet's stoppers and a tray.

Milk boiled in small bottles for twenty minutes and immediately closed by rubber, cork, or cotton stoppers will keep sweet, if put on ice, for several days.

The boiling of milk in the ordinary way is faulty. All milk for infants' and children's use should be boiled in small bottles in a water bath for twenty minutes, when it will keep much longer than if boiled in the ordinary way and the usual length of time.

The transportation of milk should take place in refrigerator cars during the summer months. This should be secured by legal enactment.

The indications for the use of sterilized milk are believed to be the following:

1. Sterilized milk should be administered to all children deprived of the breast.

2. It may be given to children suffering from diarrhœa or convalescent from cholera infantum, when milk boiled in the ordinary way is not tolerated.

3. A supply of sterilized milk is of the utmost importance for children while traveling.

The fact that sterilized milk is sure not to ferment for a considerable period of time must recommend it strongly. On the other hand, it is believed by some that boiled milk has lost some of its more delicate properties as a food; and as between fresh milk and sterilized milk, we think that no one will hesitate to prefer the former.—*Medical Record.*

### American Wares in Austria.

Mr. Charles Jonas, United States Consul at Prague, reports as follows to the State Department:

This consulate frequently receives inquiries from American commercial and trading firms as well as manufacturers touching exports to and imports from the United States, and concerning articles of American origin which could possibly find a market in this country.

Different articles sold in this market under an American label, and believed by the purchasers to be of genuine American origin, are really nothing but cheap German and British imitations. It may safely be said that numerous articles of our American hardware, mechanics' tools, farming implements, and family utensils would find a market in this country if they could be introduced and brought to the notice of the public. Of such articles, after diligent inquiry on the demands and possibilities of the local market, I would particularly name the following:

1. Improved shoemakers' tools, new patterns of tailors' shears and flatirons, latest style of fluters and plaiters.

2. Iron block planes, adjustable block planes with steel cutters, adjustable plumb and levels, sliding bevels, patent and reversible countersinks, steel screwdrivers, geared breast drills, braces, wrenches of different patterns, screw augers and steel auger bits, boring machines, bung borers, patent miter boxes, bolt cutters, lever chucks, hack saws, rip and cross-cut saws, improved sawing machines.

3. Shingling hatchets and claw hatchets, pick mattocks and grub hoes, grindstone fixtures and well wheels, hay and grain forks, manure forks, improved hay knives, cheap lawn mowers.

4. Lock hinge step ladders, wringers of new patterns, door knobs, especially the ornamental patterns, wardrobe and clothes line hooks and pulleys, brackets, flush and surface chest handles and drop handles, drawer pulls, side pulleys and screw pulleys, self-acting shade rollers, twine boxes, paper boxes.

5. Meat choppers, sausage stuffers, ice cream freezers, lemon squeezers, flour and meal sifters, and other articles for family use.

6. Reclining and rolling chairs, barber chairs, folding chairs, light American buggies and cutters, belt lacing, and, finally, different mechanical toys.

### Solid Petroleum.

Experiments are being carried on in Russia with the view of finding a process, at once practicable as well as desirable on the score of economy and cleanliness, of solidifying the petroleum used as fuel. According to the report made to the Russian government by Dr. Kauffmann, who has had the principal charge of these experiments, a successful method of accomplishing the desired result consists simply in heating the oil and afterward adding from 1 to 3 per cent of soap. The latter dissolves in the oil, and the liquid, on cooling, forms a mass having the appearance of cement and the hardness of compact tallow. The product is hard to light, burns slowly and without smoke, but develops much heat, and leaves about 2 per cent of a hard, black residuum.

© 1888 SCIENTIFIC AMERICAN, INC.

## SIMPLE EXPERIMENTS IN PHYSICS.

BY GEO. M. HOPKINS.

To all matter must be attributed two essential qualities: first, that in virtue of which it occupies space and which is known as extension, and, second, that which allows only one particle or atom of matter to occupy a given space—the property known as impenetrability. That matter occupies space is appreciated by our senses, and needs no particular proof, but that two portions of matter cannot occupy the same space at



**Fig. 1.—A HATFUL OF COTTON IN A TUMBLERFUL OF ALCOHOL.**

the same time sometimes seems anomalous, as is shown by some of the following experiments.

Into a tumbler filled with alcohol may be crowded a hatful of loose cotton without causing the alcohol to overflow. The success of the experiment depends upon the slow introduction of the cotton, allowing the alcohol to invest the fibers by capillarity, before they are fairly plunged beneath the surface of the alcohol.

In this experiment the penetration of the alcohol is only apparent; the fibers displace some of the alcohol, but the quantity is so small as not to be observable. If the cotton were compressed to the smallest possible volume, it would be found to occupy but very little space. So small a body would be incapable of raising the level of the alcohol enough to be appreciable by an ordinary observer.

A more puzzling experiment consists in slowly introducing some fine sugar into a tumblerful of warm water. A considerable quantity of sugar may be dissolved in the water without increasing its bulk.

Here the physicist is forced to acknowledge that either the water is penetrated or its atoms are so disposed as to receive the sugar between them, possibly in the same way as a scuttle filled with coal might contain also a bucketful of sand. This latter view is adhered to, and the atom or ultimate particle is held to be impenetrable.

In the case of the mixture of water and alcohol, or water and sulphuric acid, a curious phenomenon is presented. Take alcohol and water, for example. Two equal volumes of alcohol and water, when mixed, occupy less space than when separate. If the sum of the volumes of the two separate liquids is 100, the volume



**Fig. 2.—SOLUTION OF SUGAR IN WATER.**

of the mixture will be only 94. In the case of the mixture of sulphuric acid and water, the difference is greater.

An easy way to perform this experiment is to fill a narrow-necked flask up to a line which may conveniently be marked by a rubber band around the neck, then removing one-half of the water, measuring it exactly, and replacing it with a volume of alcohol exactly equal to that of the water removed. It will be found that when the liquids are mixed, the mixture will not fill the flask up to the original mark.

The only reasonable explanation of this phenomenon is that the molecules of the two liquids accommodate themselves to each other in such a manner as to reduce the pores, and thus diminish the volume of the mixture.

### COHESION.

A pretty illustration of cohesion—the force which holds the molecules of matter together—is shown in Fig. 5. In the bottom of a suitable vessel is placed a few drops of olive oil, and into the vessel is carefully



**Fig. 3.**
Representing Volume of Unmixed Alcohol and Water.



**Fig. 4.**
Reduction of Volume of Alcohol and Water Mixture.

poured a mixture of alcohol and water having the same specific gravity as the oil. The oil will be detached from the bottom of the vessel, and will in consequence of the cohesion of its particles assume a spherical form. Another method of performing this experiment is to introduce the oil into the center of the body of dilute alcohol by means of a pipette. By careful manipulation a large globule of oil may be introduced in this way. Cohesion tends to cause liquids to assume a



**Fig. 5.**
Oil Globule Suspended in Equilibrium.



**Fig. 6.**
Vial of Four Liquids.

spheroidal form, but in the case of liquids in large masses gravity causes them to assume the form of the vessel in which they are contained. The tendency of liquids to assume a spheroidal form is seen in the rain and dew drops, in liquids dropped from bottles, also in liquids thrown in drops on surfaces which they do not moisten. Water spattered upon a surface covered with lycopodium is an example of this.

### SPECIFIC GRAVITY.

The difference in the specific gravity of liquids is illustrated in a striking manner by the "vial of four liquids," shown in Fig. 6. A test tube with a foot makes



**Fig. 7.**
Egg in Fresh Water.



**Fig. 8.**
Egg Buoyed up by Salt Water.



**Fig. 9.**
Egg in Equilibrium between two Liquids of Different Densities.

a convenient receptacle for the liquids. In the bottom of the tube is placed mercury. The second liquid in order is a saturated solution of carbonate of potash. The third is alcohol, colored with a little aniline red to mark the division of the liquids more clearly. The fourth is kerosene oil. When these liquids are shaken up they mix mechanically, but when the tube is at rest the liquids quickly arrange themselves in their original order.

The egg experiment, shown in Figs. 7, 8, and 9, although without novelty, is interesting on account of its simplicity and effectiveness. Two pint tumblers, or similar vessels, are necessary for this experiment. Half fill one with water and the other with strong brine. Into the water drop an egg. It goes to the bottom (Fig. 7). An egg dropped into the brine floats (Fig. 8) By carefully pouring the brine through a long funnel or through a funnel with an attached tube, which will reach to the bottom of the tumbler containing the pure water, the water and the egg will be lifted and the egg will float in equilibrium at the middle of the tumbler.

The first experiment shows that the egg is a little more dense than pure water, the second that brine is more dense than the egg, and the third that the egg can be supported in equilibrium between two liquids of different densities.

## Precautions in Bathing.

The bathing season, though not yet advanced, has already been marked by the levy of that fatal tribute which year by year is exacted of the ignorant and the indiscreet. The recent death by drowning of a young man in the public baths at Poplar suggests one cause of accident which is too apt to be overlooked. The deceased had entered the water soon after partaking of a hearty meal, and the fatal result was attributed to cerebral congestion due to sudden immersion at such a time. What may have been the particular appearances observed after death in this case we have no means of judging, but it may be well to consider shortly some reasons why the practice of bathing soon after meals is justly condemned. Effusion of blood in or upon the brain, when it occurs in such cases as that already referred to, is probably not a primary cause of mischief, but rather a consequence founded on other circulatory and nervous disturbances. It is an evidence of eclampsia, and the physiological basis upon which this is founded consists in that inward diversion of blood toward the alimentary tract which characterizes normal digestion, the other tissues, notably the brain, being at the same time proportionally anæmic, and the action of heart and lungs impeded by a distended stomach. A natural result of cold immersion at this stage is to encourage or induce a tendency to syncope, to concentrate surface blood still more about the central organs, including the heart, which especially, if at all unequal to its duties, labors ineffectually to readjust the blood pressure, and finally succumbs with lungs and venous system engorged by passive congestion. It is as if an enemy occupied the outworks of a fortress left for a time unguarded, and forthwith paralyzed the resistance of the citadel. It is best, therefore, to wait for at least an hour and a half or two hours after a good meal before bathing. Another danger to be avoided is that of cramp. This is particularly apt to occur after severe exercise or long immersion. The effect of cold being to prolong the contraction, while exhaustion lowers both the power and the elastic recoil of muscle, it is evident that we have in a combination of these forces all that is required for the production of this dangerous condition. The obvious warning implied in these remarks requires no further admonition to impress the fact that the bather in cold water must be economical of time and free from any appreciable signs of muscular exhaustion.—*Lancet.*

## The British Association Meeting.

The general arrangements for the Bath meeting of the British Association have now been made. The first meeting will be held on Wednesday, September 5, when Sir H. E. Roscoe will resign the chair and Sir F. J. Bramwell, president-elect, will assume the presidency and deliver an address. On Thursday evening, September 6, at 8 P. M., there will be a soiree; on Friday evening, September 7, at 8:30 P. M., a discourse on "The Electrical Transmission of Power," by Professor W. E. Ayrton; on Monday evening, September 10, at 8:30 P. M., a discourse on "The Foundation Stones of the Earth's Crust," by Professor T. G. Bonney; on Tuesday evening, September 11, at 8 P. M., a soiree; on Wednesday evening, September 12, the concluding general meeting will be held at 2:30 P. M. Excursions to places of interest in the neighborhood of Bath will be made on the afternoon of Saturday, September 8, and on Thursday, September 13.

## Machinery in Mexico.

Great Britain supplies about 50 per cent of the total imports of machinery at Vera Cruz, and the United States 30 per cent, a large portion of the latter being light machinery, such as sewing machines. Of the metal goods imported, France and Germany furnish each about 30 per cent, while Great Britain only supplies 18 per cent, and the United States 15 per cent. The British Consul at Vera Cruz states that this is due to the efforts of the French and German representatives, and not to the dearness of British goods. A large portion of the American metal goods imported consists of "notions," ingenious trifles which are chiefly machine-made, and therefore cheap.

© 1888 SCIENTIFIC AMERICAN, INC.

### Miscellaneous Notes.

Admiral Lord Alcester, in a recent speech in London, made some remarks concerning the British ship builders and gun makers which have occasioned much dissatisfaction. He asserted that the British navy was much behind its neighbors in the quality of its cruisers and in the number of its modern guns. He said that two of the latest additions to the French navy (the Tage and the Cecille) were the most dangerous vessels to an enemy's commerce that had ever been launched, and that the French were building three more.

The fitting up of coast defense guns with devices for finding positions is now being agitated in England. The cost is estimated to be about $250 a gun. By means of this invention, an officer located in any prominent position is able by electrical wires to strike a ship which may be invisible from the battery itself, Major Watkin's "position finder" has been adopted by the British government, and he has received an award of $125,000 for the invention, and is also to be paid a royalty of $5,000 a year for the next ten years.

A valued correspondent, who has lately returned from Australia, states that the rich mines recently noticed in the SCIENTIFIC AMERICAN have not proved to be so remunerative as expected. Great difficulty is experienced in separating the gold. It is hard to flux so much silica as the ore contains. The shares in some of the best of these mines have greatly depreciated in value, and many of those who engaged in the mining operations have been disappointed.

A joint resolution has passed the Senate in favor of allowing Mr. Stillson Hutchins to erect, at his own expense, in the city of Washington, a colossal statue of Benjamin Franklin, in white marble, with a pedestal of Massachusetts granite. It is to be placed at the intersection of Pennsylvania Avenue, 10th and D Streets, N. W.

Mr. A. G. Fisher, of New Haven, Conn., proposes to build a cinder path from New York to New Haven, for the benefit of bicycle riders. It is to be 3 feet in width, and laid at the side of the present road; to be built, however, only where the existing roads are not good. The path will be about 70 miles in length, and the average cost of building is estimated at $75 per mile, or a total of $5,250. A little over ten per cent of the amount has already been subscribed. The various bicycle clubs are expected to assist the enterprise.

A great bicycle race recently took place from the Hotel Leland, Chicago, to Pullman, Ill., a distance of about 18 miles. There were 86 entries, and 71 contestants took the start. Arthur Lunsden, who rode a Columbia 51 inch roadster, was the winner in 54 minutes 47 seconds. He is only 19 years of age and comparatively a new rider. 53 men rode to the finish.

Dr. Neudörfer, of Vienna, has found in a substance called "creoline" a valuable antiseptic. It is a sort of tar obtained from bituminous coal by dry distillation. It is closely related to creosote, carbolic acid, resorcine, and hydrochinon. This substance has been found highly advantageous in preventing the spread of erysipelas, the pains of which it also reduces, and it effects an early cure. By its use, the subcutaneous injections of carbolic acid are not required. He has also used creoline for the treatment of ordinary flesh wounds, and for the removal of tumors. A gauze is prepared which is dipped in a solution of creoline. The doctor considers it the most trustworthy, convenient, and harmless, as well as the cheapest of antiseptic preparations.

Coal has been recommended as an earth connection for lightning rods, but Mr. J. E. Smith has ascertained by actual test with galvanometer that much depends upon the kind of coal that is selected. Out of eight or ten pieces of bituminous coal only one was found to be a fair conductor. Anthracite coal proved to be of no value as a conductor; but coke, especially the grayish kind, such as is made in coking ovens, was found to be an excellent conductor. Charcoal, on the whole, was found to be lacking in conductivity, although some specimens proved to be fair conductors.

Machines for registering the amount of cash received are among the new appurtenances of well regulated retail establishments in this city. The operator presses a key, which turns the register, counts and records the amount paid into the money drawer. When the day's work is done, the machine shows the total amount of cash received, and the cash in the drawer should correspond with the figures on the register. It is said to be a very convenient and valuable machine.

A physician thinks that a law should be made to prohibit the use of galvanized iron lemonade squeezers. He says that every time a lemon is squeezed in one of these machines the acid of the lemon, coming in contact with the zinc, dissolves the same and forms a poisonous salt. Zinc is a metal which is easily attacked by the weakest acids, and no article of food or drink should ever be allowed to come in contact with it.

We have seen a specimen of a new campaign torch which promises to become quite popular. It is made from a combined composition of inflammable matter, and when lighted, burns dry; that is to say, it is free from grease, does not run, and gives off no bad odor. It may be stuck on the end of a handle or pole, can be carried in the pocket, and is always ready for use. It yields a large flame. It burns 30 minutes, and three of them (with the stick) form an outfit suitable for any political procession. They are made by J. A. Heckman, of this city.

At the recent commencement of Stevens Institute of Technology, Hoboken, N. J., it was announced by Mr. S. B. Dod, president of the board of trustees, that he had received from President Henry Morton $10,000 as the first installment toward the endowment of the chair of engineering practice recently created, and now occupied by Mr. Coleman Sellers, of Philadelphia. President Morton has been the chief of the establishment ever since its opening, and to the zeal and exalted ability of his management the success of the Institute is eminently due. His personal labors for the advancement of the institution have been most assiduous, while his pecuniary contributions have been numerous and generous. We believe he has endowed several other important chairs, having contributed altogether somewhere about $50,000. No man stands higher in the rank of prominent educationists than Henry Morton. No institution of learning enjoys a better reputation for excellence and thoroughness than Stevens Institute.

An important decision was lately made in the United States Court at Indianapolis, by Judge Gresham, in the case of Charles F. Brush *vs.* John Owens and others. It was claimed by the patentees that the patent covered the use of the electro-magnet, but the judge held the patent to be limited only to solenoids.

Dr. Donald C. Hood has collected many facts relating to the use of salicylic acid for rheumatism. Of 728 patients treated with salicylates, 523 were relieved of their pains within seven days; whereas, of 612 patients treated by other methods, only 140 were relieved within the same time.

The use of saccharine as a substitute for sugar is not considered safe from a medical point of view. Dr. Worms, in a communication to the French Academy of Medicine, states that of several patients who made use of saccharine by his advice, all but one were soon compelled to give it up on account of the occurrence of dyspeptic symptoms, nausea, loss of appetite, etc. It is usually not until after the substance has been taken for from ten to fifteen days that it manifests its evil influence. It then appears to accumulate in the system.

One of the pipes of the Standard Oil Company, that brings oil from the petroleum regions of Pennsylvania to New York, a distance of 400 miles, recently burst in Vernon township, Sussex County, N. J. Before the mischief was discovered the soil in the vicinity of the broken pipe became saturated and poisoned with crude oil, and ruined for the present. A large quantity of oil flowed into the neighboring streams, and the fishes died by thousands. It is said the farmers will bring suits for damages against the Standard Oil Company, for injuries sustained by this oil flood.

Mr. A. W. Van Dorston estimates there are 1,000,000 cars in the United States, the couplers of which must be changed if the standard of the Master Car Builders' Association is generally adopted. He figures the cost at $28.50 a car, which would make the entire expense of the change $28,500,000. Supposing the present couplers—which must be displaced—to have cost $15 per car, or $15,000,000 for the entire equipment, and that the destruction of cars and car trucks, the wrecks from broken links, the loss of pins and links, the death rate from the free slack and going between the cars to place and replace the links, costs annually $17,000,000 more, or $32,000,000 in all, still he thinks the automatic coupler must be regarded as decidedly the cheapest.

The building of the Edison Electric Illuminating Company in Boston, Mass., was lately destroyed by fire, although it was supposed to be fire proof. It was built of brick and iron, but unfortunately, they laid down wooden floors and sheathed the walls and ceilings with varnished wood. When the fire broke out, the wood produced such a tremendous heat as to warp the iron beams and quickly caused the destruction of the building. Every dynamo in the station was destroyed—the engines and boilers, however, were not injured. New dynamos were telegraphed for at once, and on the Monday night succeeding the fire—which took place on Saturday night—the establishment was again in operation, and the Edison lights throughout the city were working as usual. The conflagration was caused by the overheating of one of the equalizers, by having more current pass through it than it was designed to carry. The fire was thus communicated to the adjoining woodwork.

On the Lehigh Valley Railroad, at Glen Onoko, Pa., there is a switch connection consisting of a gas pipe which extends 1,255 feet from the point where it is operated.

In Oakland, Cal., and other places, compressed air is now successfully used for operating switches having an interlocking apparatus. The system is, in fact, very extensively used on several of our principal railways. It takes up less space than mechanical locking machinery, and the labor of working it is very light. The ground connections can be buried out of the way, and can be led out from the tower in any way most convenient.

"Emmensite" is the name of a new explosive discovered by Dr. Stephen M. Emmens, which has lately been tried with much success. The doctor claims that by the use of one of his cartridges and a gun 40 feet long he can throw a projectile to a distance of 27 miles. We should like to see him do it. At a recent trial with a rifle at 100 yards, a ball fired by a cartridge containing 70 grains of powder penetrated three planks of pine wood 1¼ inches thick; while a charge of 15 grains of emmensite drove the bullets through five of these planks. A shell weighing 66½ pounds was thrown by a half ounce of emmensite twice as high into the air as by the same quantity of dynamite or one and one-half ounces of gunpowder. Various other experiments were made, all showing the superior power of the new explosive.

The bill now before the House of Representatives, for the establishment of a Court of Patent Appeals, is very favorably regarded by several of the members of the Supreme Court of the United States, also by the Commissioner of Patents, and others. One object of the new court is to relieve the Supreme Court from much of the labor now involved in the decision of patent cases. The new court is to consist of a chief judge and four associate judges, who are to have a salary of $8,000 each. The court is also to appoint a clerk and marshal, with various deputies; also a reporter, who is to cause the decisions of the court to be printed, at an expense not exceeding $4 per volume. The court is to hold one term annually.

This Court of Patent Appeals is to have appellate jurisdiction from the courts of the United States having original jurisdiction of cases touching patents, copyrights, trade marks and labels; also from the Commissioner of Patents touching the patentability of invention, priority of invention among several claimants for patents upon the same invention, and in all cases of reissue; also in the registration of trade marks and labels, and the rights of conflicting claimants therefor. All such cases formerly appealable to the Supreme Court are to be heard on appeal to the Court of Patent Appeals. All cases touching patents, trade marks, copyrights, or labels now pending before the Supreme Court are to be transferred to the Court of Patent Appeals.

### Death by Electricity.

Dr. Richardson writes on this subject in the *Asclepiad* as follows: "In some researches on the application of the electric discharge for the painless extinction of the lives of animals to be used as food, the details of which I recorded in the *Medical Times and Gazette* for the year 1869, this mode of death was anything but certain in its effects. Sheep stricken apparently into instant and irrevocable death by electricity, after a few minutes showed signs of life, and if they had not been dispatched in the ordinary way by the knife would have been restored to consciousness. The same fact has been observed in attempts to kill dogs by the electric shock, and I once published an instance in which a large dog, struck into perfect unconsciousness by the stroke from a powerful battery, was submitted to a surgical operation while lying, to all appearances, dead, and was yet so little affected as to make an easy and sound recovery. It need not be inferred from such facts as these that the electric shock will not kill at one discharge—in most cases it will—but, exceptionally, instead of killing outright it will simply stun, and may induce the semblance of death instead of the real event. It will be only common humanity, therefore, for the authorities of New York, when they begin to give the *coup de grace* by the electric shock, to supplement the process by a *post mortem* examination of the victims, so that the act may not be crowned by burying the victims alive."

THE Springfield, Mass., *Good Housekeeping* offers twenty-five dollars for the best buffalo bug extinguisher, twenty-five dollars for the best bed bug finisher, twenty-five dollars for the best moth eradicator, and twenty-five dollars for the best fly and flea exterminator.

© 1888 SCIENTIFIC AMERICAN, INC.

## ENGINEERING INVENTIONS.

A steam engine has been patented by Messrs. Johann C. Grabner, of Kupferhammer, and Henry Ruperti, of Brackwede, Prussia, Germany. It is a cylinder and piston motor wherein the distribution of the motor liquid alternately to either side of the piston is effected without the use of valves or slides, by means of specially constructed passages and ports in the cylinders and their pistons.

A mechanical movement has been patented by Mr. Benjamin F. Andrews, of Myers, Mo. It is for converting reciprocating or oscillating motion into rotary motion, and the invention consists in certain novel constructions and combinations of parts, designed to be available for the propelling of vessels or vehicles, for running machines, or to be applied to engines.

A safety guard for car trucks has been patented by Mr. William H. Walker, of Martinez, Ga. Combined with the truck frame is a cross-braced connection carrying shoes at each downwardly bent end, such shoes being supported just above the rail in front of the wheel, and being flanged, so that they would drop on the rail and serve as a brake in case of breakage of a wheel or axle.

A carburetor has been patented by Messrs. Chester S. King and Edward G. Brown, of Smethport, Pa. It is a combined gas engine and carbureting apparatus, the latter operating the engine and supplying carbureted air to be mixed with air to form an explosive mixture for use in the engine, the speed of the engine controlling the speed of the carburetor, the supply of hydrocarbon thereto, and the supply of gas to the engine.

## MISCELLANEOUS INVENTIONS.

A coffin has been patented by Messrs. James P. and John S. Mahon, of New York City. This invention provides a sheet metal coffin which can be easily and cheaply manufactured, can be tightly closed, and is designed to possess the qualities of strength and durability with extreme lightness and portability.

A mail pouch has been patented by Mr. George J. Bedford, of Anamosa, Iowa. It is for the transport of registered letters, securities, etc., and is metal lined and arranged for connection with a metallic belt to be placed about the person of the messenger, and provided with any proper form of lock.

A dump car has been patented by Mr. Joseph Odorizzi, of Trinidad, Col. It has a gate or door at one end hinged at its upper edge upon a horizontal axis by means of a shaft journaled in the sides of the car, the invention covering a simple and efficient means for locking and unlocking the door, through which the car is dumped.

A double harness saddle and yoke has been patented by Mr. Louis A. Mancini, of Montclair, N. J. This invention relates to a device in which the harness saddles are connected together and are adjustable upon their connection, being designed to allow for the movements of the horses, and permit them to move freely and prevent friction of the saddle.

A drill has been patented by Mr. John C. Godwin, of Royse City, Texas. It is specially adapted for turning the drill tool for boring artesian wells, and for prospecting purposes, the invention consisting of a disk connected with the drilling tool, and having a backward and forward turning motion imparted by an especial mechanism.

A glove has been patented by Mr. William Vaughan, of Torrington, Devon County, England. This invention relates especially to gloves made of woven material, and consists in strengthening and protecting the tips of the fingers and tongues by rows of stitching, either in straight or curved lines, the chain stitch being preferred.

A stirrup has been patented by Mr. Thomas J. Taylor, of Howell, Tenn. It consists of a curved piece of wood extending from under the foot around the toe and up above the instep, with a bolt or cross bar for connecting it with the supporting strap, the inside of the curved stirrup frame being formed of leather or other flexible material.

A gate has been patented by Mr. John Flinner, of Boling, Kansas. It is of that class which is hinged about a horizontal axis at one end and at its lowest corner, so as to rise vertically about this center, and is connected by rods with levers mounted upon posts upon opposite sides of the gate, whereby the gate may be operated from passing vehicles without the necessity of alighting therefrom.

A wall paper exhibitor has been patented by Mr. M. Otto Smith, of Creighton, Mo. It is adapted for arrangement with shelving having a projecting cornice at the top, and designed to hold the paper so that it may be unwound from sample rolls, to exhibit it as it will appear on the walls, while it may be readily rewound, and allow free access to the goods on the shelves.

An improvement designed to simplify the construction of plumes, tassels, etc., forms the subject of a patent issued to Mr. Ralph W. E. Aldrich, of Northampton, Mass. The plume is made of Cotswold hide, tanned with the hair on, and bleached or dyed as desired, to be attached in any approved manner to an ornament, instead of the usual fringe of silk, cotton, etc.

A lamp burner has been patented by Mr. Arthur Cautius, of Berlin, Germany. The wick tube consists of two concentric tubes with a space between them for the wick, the inner tube being shorter and the outer one longer and provided with a flange covering the top of the wick, the burning portion of which will be on the inside instead of the top, between the flange and the top of the inner tube.

A vegetable slicer has been patented by Mr. Vincent Bissig, of Greenville, N. J. It is of that kind used for cutting potatoes and similar edibles in a continuous or spiral manner, in which the vegetable is held by one hand and is speared by an entering screw having a knife attached at its outer end, which is rotated to slice the vegetable, the screw keeping up the feed.

A cock for fire extinguishers has been patented by Mr. Charles C. Connell, of Haydenville, Mass. It is of the kind adapted to be opened by the action of heat to permit the escape of a liquid held under pressure, the valve having on its outer end a lever engaging a recess formed in a thin plate of metal that heats at a low temperature, the plate being held in its position by an easily melting solder.

A fluid drawing and measuring device has been patented by Mr. John A. Kendall, of Maysville, Mo. It consists of a measuring cylinder adapted to be placed in the bottom of the tank or vessel, through the sides of which pass connecting pipes connected on the outside with a four-way cock, there being a piston held to slide in the inner cylinder, with other novel features, for automatically measuring coal oil, etc.


# SCIENTIFIC AMERICAN BUILDING EDITION.

**JULY NUMBER.—(No. 33.)**

TABLE OF CONTENTS.

1. Elegant plate in colors of a cottage of moderate cost, with floor plans, details, etc.
2. Plate in colors, with floor plans, details, etc., for a suburban dwelling. Cost, six thousand dollars.
3. Floor plans and perspective view of a suburban cottage erected at Fordham Heights, New York City. Cost, five thousand dollars.
4. A Queen Anne, lately erected at Asbury Park, N. J. Cost, complete, fourteen hundred dollars. Perspective and floor plans.
5. Design and floor plans for a carriage house and barn.
6. Perspective of an attractive cottage at Jekyl Island, Ga.
7. Design for a small cottage costing two thousand dollars. Perspective elevations and floor plans.
8. A church at Nashville, Tenn.
9. Illustration of the Chapel of Pocito, Mexico.
10. Lich gate or cemetery entrance.
11. Page of engravings showing some attractive dwellings in Connecticut.
12. An attractive cottage lately erected at Asbury Park, N. J., at a cost of eighteen hundred and fifty dollars, complete. Plans and perspective.
13. A row of twelve hundred dollar houses lately erected at Kingsbridge, New York City. Plans and perspective.
14. Illustration of U. S. Court House and Post Office, Troy, N. Y.
15. Design for the new U. S. Court House and Post Office at Williamsport, Pa.
16. Engraving of the new U. S. Court House and Post Office, Chattanooga, Tenn.
17. View of the oldest cottage at Asbury Park, N. J.
18. Plans and perspective view of a cozy little seashore cottage lately built at Ocean Grove, N. J. Cost four hundred dollars.
19. A modern house built at Asbury Park, N. J., at a cost of two thousand dollars. Plans and perspective.
20. Illustration of the new U. S. Court House and Post Office at Oshkosh, Wis.
21. Perspective and floor plans for a pleasant cottage to cost from eighteen hundred to two thousand dollars.
22. A cottage lately built on Monroe Av., Asbury Park, N. J., for one thousand and fifty dollars. Plans and perspective.
23. Perspective view of a design for a museum, Pelz and Griebel, architects. Full page engraving.
24. Miscellaneous contents: Riche's pantograph, illustrated.—Areas of different parks.—Paint work.—Sawdust.—The chimney shaft.—The age of stars.—Wood that will not blaze.—Bricks of blown glass.—Turning and polishing marble.—Decorative joinery.—Villas and their doorways.—The law of trespass.—Water for household use.—Hydraulic mortars and cements.—The Durango tunnel.—Slate bricks.—Houses in Seville.—Shells as a decorative element.—Ancient and modern mortars.—Treatment of hardwood floors.—A selection of lilies.—Undesirable town houses.—Richmond's Victor steam heater, illustrated.—Cheap buildings in China.—Improved fans, ventilators, etc., for buildings and for mechanical uses, illustrated.—An economical steam and hot water heating boiler, illustrated.—An improved dumb waiter, illustrated.—A composite steel wire door mat, illustrated.—Domestic conveniences possible with a hand force pump, illustrated.—New variety moulder and shaper, illustrated.—How to fit up a recess.—The Boynton furnaces, ranges, and heaters, illustrated.—Cook's new extension beam trammels illustrated.

The Scientific American Architects and Builders Edition is issued monthly. $2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming, practically, a large and splendid MAGAZINE OF ARCHITECTURE, richly adorned with elegant plates in colors and with fine engravings, illustrating the most interesting examples of Modern Architectural Construction and allied subjects.

The Fullness, Richness, Cheapness, and Convenience of this work have won for it the LARGEST CIRCULATION of any Architectural publication in the world. Sold by all newsdealers.

MUNN & CO., PUBLISHERS,
361 Broadway, New York.


## Business and Personal.

*The charge for Insertion under this head is One Dollar a line for each insertion; about eight words to a line. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.*


Rotary veneer basket and fruit package machinery. I. E. Merritt Co., Lockport, N. Y.

Wanted—One or two sets of chasers for crushing flint. From 5 to 5½ feet diameter. Jacob Kugler, Trenton, N. J.

John M. Horr, fret sawyer. North Dana, Mass.

The best *Coffee* roasters, coolers, stoners, separators, polishers, scourers, glossing apparatus, milling and peaberry machines; also rice and macaroni machinery, are built by The Hungerford Co., 69 Cortlandt Street, New York.

Safety water columns. Cheaper than explosions or burned boilers. For illustrated price list, Reliance Gauge Co., Cleveland, O.

Steam Pipe Covering, Sectional and Plastic. Write for Pamphlet. Jno. A. McConnell & Co., 69 Water St., Pittsburgh, Pa.

The Diamond Prospecting Co., 74 and 76 W. Lake St., Chicago, Ill., general agents for the Sullivan diamond prospecting drills.

For the latest improved diamond prospecting drills, address the M. C. Bullock Mfg. Co., 138 Jackson St., Chicago, Ill.

Nickel Plating.—Manufacturers of pure nickel anodes, pure nickel salts, polishing compositions, etc. $100 "*Little Wonder.*" A perfect Electro Plating Machine. Agents of the new Dip Lacquer Kristaline. Complete outfit for plating, etc. Hanson, Van Winkle & Co., Newark, N. J., and 92 and 94 Liberty St., New York.

Perforated metals of all kinds for all purposes. The Robert Aitchison Perforated Metal Co., Chicago, Ill.

The *Railroad Gazette*, handsomely illustrated, published weekly, at 73 Broadway, New York. Specimen copies free. Send for catalogue of railroad books.

The Knowles Steam Pump Works, 113 Federal St., Boston, and 93 Liberty St., New York, have just issued a new catalogue, in which are many new and improved forms of Pumping Machinery of the single and duplex, steam and power type. This catalogue will be mailed free of charge on application.

*Link Belting* and Wheels. Link Belt M. Co., Chicago.

Iron Planer, Lathe, Drill, and other machine tools of modern design. New Haven Mfg. Co., New Haven, Conn.

Presses & Dies. Ferracute Mach. Co., Bridgeton, N. J.

Supplement Catalogue.—Persons in pursuit of information of any special engineering, mechanical, or scientific subject, can have catalogue of contents of the SCIENTIFIC AMERICAN SUPPLEMENT sent to them free. The SUPPLEMENT contains lengthy articles embracing the whole range of engineering, mechanics, and physical science. Address Munn & Co., Publishers, New York.

The Holly Manufacturing Co., of Lockport, N. Y., will send their pamphlet, describing water works machinery, and containing reports of tests, on application.

Lockwood's Dictionary of Terms used in the practice of Mechanical Engineering, embracing those current in the drawing office, pattern shop, foundry, fitting, turning, smith's and boiler shop, etc., comprising over 6,000 definitions. Edited by a foreman patternmaker. 1888. Price, $3.00. For sale by Munn & Co., 361 Broadway, New York.

Duplex Steam Pumps. Volker & Felthousen Co., Buffalo, N. Y.

Iron, Steel, and Copper Drop Forgings of every description. Billings & Spencer Co., Hartford, Conn.

For best forges, blowers, exhausters, hand and power drills address Buffalo Forge Co., Buffalo, N. Y.

We are sole manufacturers of the Fibrous Asbestos Removable Pipe and Boiler Coverings. We make pure asbestos goods of all kinds. The Chalmers-Spence Co., 419 and 425 East 8th Street, New York.

The Improved Hydraulic Jacks, Punches, and Tube Expanders. R. Dudgeon, 24 Columbia St., New York.

Hoisting Engines, Friction Clutch Pulleys, Cut-off Couplings. The D. Frisbie Co., 112 Liberty St., N. Y.

Tight and Slack Barrel Machinery a specialty. John Greenwood & Co., Rochester, N.Y. See illus. adv., p. 28.

No. 11 planer and matcher. All kinds of woodworking machinery. C. B. Rogers & Co., Norwich, Conn.

☞Send for new and complete catalogue of Scientific and other Books for sale by Munn & Co., 361 Broadway, New York. Free on application.


## NEW BOOKS AND PUBLICATIONS.

A SYSTEM OF EASY LETTERING. J. Howard Cromwell, Ph.B. E. & F. N. Spon. New York, 1888. Pp. 26. Price fifty cents.

This little work gives twenty-six different forms of alphabets, all constructed on the same general system. The space to be lettered is to be divided into parallelograms or squares, as the case may be, and within these as a guide the different letters are drawn and inked. The guide squares, which have been made in pencil, are then erased, leaving the final letters. On so simple a basis as this quite a variety of effects are produced in flat and block letters.

THE COURSE INDICATOR LIGHTS. By C. A. Lidstone. Calcutta, 1885. Pp. 4. With colored diagrams.

A simple system of indicating the course of vessels at night, by supplementing the present sailing lights with four additional ones, is here described. The system is a good one and has much to recommend it. It introduces, naturally, some elements of confusion to an ignorant sailing master, but leaves untouched the present system, if he chooses not to notice the extra lamps. It is clear that some advanced system is needed to prevent collisions at sea, and this certainly seems well adapted for that end.

☞Any of the above books may be purchased through this office. Send for new book catalogue just published.

Address MUNN & Co., 361 Broadway, New York.


## TO INVENTORS.

An experience of forty years, and the preparation of more than one hundred thousand applications for patents at home and abroad, enable us to understand the laws and practice on both continents, and to possess unequaled facilities for procuring patents everywhere. A synopsis of the patent laws of the United States and all foreign countries may be had on application, and persons contemplating the securing of patents, either at home or abroad, are invited to write to this office for prices, which are low, in accordance with the times and our extensive facilities for conducting the business. Address MUNN & CO., office SCIENTIFIC AMERICAN, 361 Broadway, New York.


# INDEX OF INVENTIONS

**For which Letters Patent of the United States were Granted**

**June 26, 1888,**

**AND EACH BEARING THAT DATE.**

[See note at end of list about copies of these patents.]

Air brake, E. Andrews ..... 385,224
Air brake, H. S. Park ..... 385,198
Anchors, machine for making building, J. Russell 385,140
Animal releasing device, J. D. & C. A. Sullivan ..... 385,077
Animal trap, J. T. Belden ..... 385,086
Axle box lids, die for making car, G. W. Morris ..... 385,194
Axle lubricator, car, J. J. Stever ..... 385,213
Bag. See Traveling bag.
Bags and satchels, fastening for hand, G. Crouch. 385,243
Baling press, Meyer & Sutphen ..... 384,993
Baling press, W. F. & G. W. Shafer ..... 385,207
Barrels, apparatus for pitching, L. & O. Haggenmiller ..... 385,178
Baton or club, policeman's, E. D. Bean ..... 385,293
Batteries, electrolyte for galvanic, B. J. Wheelock ..... 385,028
Battery. See Electric battery. Galvanic battery. Secondary battery.
Battery zinc, J. Doyle ..... 385,254
Bed or bed bottom, spring, F. M. Jeffery ..... 385,118
Bedstead fastener, P. Forg ..... 385,260
Bell, call, J. P. Connell ..... 385,166
Bell ringing mechanism, J. Z. White ..... 385,029
Bicycle pedal, W. E. Smith ..... 385,074
Blind, inside, H. A. Benedict ..... 384,954
Boiler. See Steam boiler.
Boiler, F. W. Dean ..... 385,102
Bolt heading machine, E. N. Whitaker ..... 385,080
Boot or shoe G. Valiant ..... 385,218
Boot treeing machine, G. W. Copeland ..... 385,298
Bottle closure, W. Rodiger ..... 385,011
Box. See Journal box. Photographic developing box. Toy money box.
Box lid, W. D. Harrison ..... 385,305
Bracelet chain, G. A. Lenau ..... 385,313
Brake. See Air brake. Car brake.
Brick and tile machines, lubricating die for, R. Niedergesaess ..... 385,317
Brick kiln, G. W. Sharer ..... 385,209
Bridles, check piece for, O. Botsford ..... 385,090
Broom head, W. W. Thompson ..... 385,217
Buckle, back band, R. T. Semmes ..... 385,206
Buckle, safety, J. G. Kitchell ..... 384,984
Buckle, trace, B. C. Smith ..... 385,146
Bustle, V. H. Buschmann ..... 385,296
Buttonhole flies, mechanism for stamping and cutting out, Valiant & Dancel ..... 385,219
Cable grip, F. H. Morse ..... 385,195
Calendar, J. Cussons ..... 385,245
Can. See Oil can.
Can opener and sheet metal cutter, E. Hawes ..... 384,973
Cane, machine for cutting sugar, L. Bon ..... 385,234
Car brake, A. Reese ..... 385,007
Car coupling, W. M. Cutter ..... 385,101
Car coupling, R. H. Dowling ..... 385,301
Car coupling, E. L. Keeler ..... 385,185
Car coupling, Lorraine & Aubin (r) ..... 10,941
Car coupling, H. S. McKague ..... 385,129
Car coupling, F. W. Parsons ..... 385,000
Car coupling, H. S. Sanders ..... 385,204
Car coupling, Ward & Fallgatter ..... 385,027
Car door, grain, A. B. Taylor ..... 385,021
Car, railway, C. W. Littlefield ..... 384,987
Car spring, railway, B. J. La Mothe ..... 385,061
Car step, F. A. Stanwood ..... 385,017
Cars, metallic platform for railway, J. T. Goodfellow ..... 385,177
Carburetor, King & Brown ..... 385,121
Carpenter's framing gauge, L. P. Pickering ..... 385,321
Carpenter's gauge, A. Laporte ..... 385,124
Carriage wheel fender, G. C. W. Magruder ..... 384,989
Carrier. See Cash and package carrier. Cash carrier. Hay carrier.
Carving machine, S. F. Moore ..... 384,995
Case. See Piano case.
Cash and package carrier, W. T. Geltz ..... 385,110
Cash carrier, N. Newman ..... 385,196
Cash indicator, register, and recorder, C. B. Hopkins ..... 385,265
Cash register and indicator, Patterson & Davis ..... 385,199
Casks or barrels, agitator for, G. M. Thompson ..... 385,151
Caster for stoves, etc., A. H. Conn ..... 385,240
Cellars waterproof, rendering, F. J. De Borger ..... 385,103
Cigar cutter, Young & Shertzer ..... 385,221
Clapper or rattler device, O. Pagan ..... 385,002
Clasp, J. Merriam ..... 385,192
Cleaner. See Drain cleaner. Grain cleaner.
Clip. See Stocking suspender clip.
Clock dial, A. Bannatyne ..... 385,160
Closet. See Water closet.
Cloth cutting machine, G. J. W. Galster ..... 385,050
Clutch, J. Bruyiere ..... 385,093
Clutch, E. B. Lake ..... 385,123
Coats, making, W. Cohen ..... 385,096
Cock, gauge, Hodges & Davie ..... 385,052
Compass, electric alarm, H. A. Chase ..... 385,043
Compass, mariner's recording, H. A. Chase ..... 385,042
Cotton press, L. Miller ..... 385,193
Coupling. See Car coupling. Friction coupling. Pipe coupling.
Checkrein attachment for harness, H. J. Wing ..... 385,082
Checkrein hook, J. H. Hill ..... 385,115
Cuff holder, E. L. Clancy ..... 385,239
Cultivator shovel, D. Leigh ..... 385,275
Cuspidor, Annen & Fox ..... 385,159
Cutter. See Cigar cutter. Rod cutter.

© 1888 SCIENTIFIC AMERICAN, INC.

Cutter head. G. S. Shimer ..... 385,325
Dental hammer and plugger, electro-magnetic, P. Helmer (r) ..... 10,940
Dental plate, J. F. Sargent ..... 385,142
Desk and organ, combined, O. E. & G. C. Wick ..... 385,081
Desk, school, E. Murray ..... 385,316
Dibble, T Seller ..... 385,324
Digger. See Potato digger.
Dividers, spring, J. F. Guthrie, Jr ..... 384,971
Door mat, A. M. Cooley ..... 385,044
Dough cutting machine, A. Day ..... 384,964
Drain cleaner, convertible, E. J. Robinson ..... 385,283
Drier. See Salt drier.
Drier, G. W. Sharer ..... 385,208
Drill, J. C. Godwin ..... 385,111
Drilling, feeding device for, Lodge & Dreses ..... 385,063
Drilling rig, G. Corbett ..... 385,241
Drilling tool, A. Benzie ..... 385,088
Drum, friction, H. J. McKeown ..... 385,191
Dust collector, J. S. Ash ..... 385,037
Dust collector, C. M. Hardenbergh ..... 385,263
Duster, feather, G. M. Richmond ..... 385,070
Eaves trough hanger, H. T. & H. O. Lawrence ..... 384,985
Educational apparatus, J. Dushane ..... 385,046
Electric battery, E. M. Hewitt ..... 385,308
Electric cut-out, C. G. Perkins ..... 385,067
Electric light system, B. E. Sunny ..... 385,020
Electric machinery, dynamo, A. Reckenzaun ..... 385,068
Electric switch, P. J. Tracy ..... 385,023
Electrical connector, Stitzel & Weinedel ..... 385,215
Electrical distribution, system of, T. A. Edison ..... 385,173
Electrical purposes, switch for, W. A. Carey ..... 385,041
Electricity and purifying water, generating, J. E. Siebel ..... 385,145
Engine. See Rotary cylinder engine. Steam engine.
Envelope tablet, H. Phillips ..... 385,320
Evaporator, N. B. Rice ..... 385,202
Fabric. See Roofing fabric.
Farm gate, P. Dyer ..... 385,302
Faucet, E. P. J. Freeman ..... 385,108
Fence machine, C. F. Gillet ..... 385,304
Fences, lightning escape for wire, A. Cockrell ..... 385,095
Filling, lining, and covering material, H. W. Johns ..... 385,120
Filter, F. K. Way ..... 385,333
Finger ring, W. P. Sinnock ..... 385,073
Firearm, magazine, J. M. & M. S. Browning ..... 385,238
Fire cracker cannon, J. J. Loud ..... 385,127
Fire cracker holder, A. Willis ..... 385,032
Flask. See Moulder's snap flask.
Flour mill, J. J. Faulkner ..... 385,175
Flushing tank, automatic, H. L. Howe ..... 384,978
Fodder binder, W. Leupold ..... 385,126
Food for cattle, horses, and swine, composition, W. Wernich ..... 385,220
Forceps, etc., clamping device for, F. A. Stohlmann ..... 385,076
Fork. See Hay or straw grappling fork.
Foundations, frost protector for, H. H. Morgan ..... 385,278
Frame. See Quilting frame.
Friction coupling, O. Kromer ..... 385,122
Furnace. See Ore smelting furnace.
Furnaces, apparatus for charging billets, bars, etc., into, F. H. Daniels ..... 385,248 to 385,250
Furnaces, apparatus for charging billets or bars into heating, F. H. Daniels ..... 385,251
Furnaces, device for mixing air and gas for, H. Schlimme ..... 385,072
Gauge. See Carpenter's gauge. Carpenter's framing gauge.
Galvanic battery, Brown & Clark ..... 384,958
Galvanic battery, E. E. Starr ..... 385,147
Game, G. P. Lathrop ..... 385,190
Garment supporter, F. E. Bright ..... 385,237
Garment, ventilated, E. S. Helwitz ..... 385,306
Gas fixtures, cock for, J. Prentice ..... 385,134
Gas pressure regulator and cut-off, G. S. Faulkner ..... 384,967
Gate. See Farm gate.
Gimp machine, G. Faustmann ..... 385,048
Glove, W. Vaughan ..... 385,154
Glove fastener, W. D. Thompson ..... 385,331
Governor, J. W. Thompson ..... 385,152
Grain binder, Kennedy & Anderson ..... 385,059
Grain cleaner, J. S. Ash ..... 385,036
Grain meter, G. H. Kamman ..... 384,983
Grinding mill, M. J. Althouse ..... 385,025
Grooving apparatus for cardboard, leather, and like material, T. Remus ..... 385,201
Hammer for blacksmiths, spring, Stewart & Wiswall ..... 385,018
Hand press, domestic, J. W. Condon *et al* ..... 385,165
Hanger. See Eaves trough hanger.
Harness, trace lock for, L. Anderson ..... 385,233
Harrow, J. W. Dobyns ..... 384,966
Harvester, G. Esterly ..... 385,047
Harvester, corn, G. B. & J. T. Snow ..... 385,286
Harvester, grain binding, A. O. Slentz ..... 385,285
Harvesters, cutting apparatus for, Blair & Bush ..... 385,164
Hat and coat rack, folding, G. D. Tolman ..... 385,153
Hat, ventilated, M. Postlethwaite ..... 385,282
Hats, sweat band for, T. W. Bracher ..... 385,092
Hay cap, J. Brady ..... 384,957
Hay carrier, G. H. Fowler ..... 384,968
Hay loader, W. S. Nichols ..... 385,281
Hay or straw grappling fork, E. V. R. Gardner ..... 384,970
Hay rake and ricker, combined, R. O. Davis ..... 385,252
Hay sling, A. & C. A. Church ..... 384,960
Heater. See Water heater.
Heel burnisher, C. J. Addy ..... 385,291
Hinge, J. Wien ..... 385,156
Hinge for traveling bags, etc., C. Reinisch ..... 385,133
Hinge for trunks, bags, etc., stay, W. Durand ..... 385,255
Hinge, lock, T. S. Beebe ..... 385,162
Hinge, spring, H. P. Kochsmeier ..... 385,312
Holder. See Cuff holder. Fire cracker holder. Lamp holder. Music holder. Rein holder.
Hook. See Checkrein hook. Snap hook.
Horse detacher, G. T. Parker ..... 385,132
House interiors, finishing of, W. J. Boda ..... 385,238
Ice or refrigerating machine, F. W. Wolf ..... 385,157
Identifying device, E. R. Fitch ..... 385,106
Indicator. See Cash indicator. Station indicator.
Iron, manufacturing oxide of, A. C. Bradley ..... 385,235
Joint. See Rail joint.
Journal bearing, anti-friction, J. W. Hyatt, 385,266, 385,267
Journal box, W. B. Turner ..... 385,288
Kiln. See Brick kiln. Malt kiln.
Knitting machine, D. C. Bellis ..... 385,163
Knitting machines, reversing mechanism for, H. C. Rightmire ..... 385,322
Lamp holder, incandescent, W. A. Carey ..... 385,039
Lantern supporter, C. Smith ..... 385,015
Life buoy, reel, A. Rust ..... 385,323
Lock. See Permutation lock.
Loom let-off mechanism, J. Morton ..... 385,279
Lubricator. See Axle lubricator.
Lubricator, W. A. Carey ..... 385,040
**Malt kiln, G. Reininghaus ..... 385,137**
**Marine signal, W. G. Spiegel ..... 385,016**
Mat. See Door mat.
Measuring device, automatic water, W. Lammers 385,274
Measuring tank for oil, Lindsay & Ross ..... 384,986
Measuring vessel, W. Evans, Jr ..... 385,303
Mechanical movement, B. F. Andrews ..... 385,084
Meter. See Grain meter.
Milk preserving machine, G. Roth ..... 385,013
Mill. See Flour mill. Grinding mill.
Mould, J. Hemphill ..... 384,976
Moulder's snap flask, E. Riley ..... 385,203
Mop wringer, J. A. Crandall ..... 385,170
Motor. See Wave power motor.
Mower, lawn, E. E. Johnson ..... 385,272
Mug, Z. T. Hall ..... 385,179
Multiple switch boards, test system for, C. E. Scribner ..... 385,205
Music holder, E. W. Robinson ..... 385,010
Nail plate feeder, J. C. Gould ..... 385,112
Nut machine, F. Lackner ..... 385,187, 385,188
Nut machine, A. Marland ..... 385,128
Oil cakes, moulding press for, O. P. Bushnell ..... 385,094
Oil can, E. G. Cushman ..... 385,244
Oil can, Straffin & Robertson ..... 385,328
Ore smelting furnace, C. W. Barry ..... 385,229
Oyster spat, obtaining, O. B. Beach ..... 385,161
Package for butter or similar material, S. Smyth ..... 385,075
Paddlewheels, feathering, D. J. Blasier ..... 385,232
Pail, dinner, F. G. O. Ehle ..... 385,257
Papers, etc., return packet for the transmission of, W. B. Nolley ..... 385,197
Pasting apparatus, Lorenz & Honiss ..... 385,064
Permutation lock, J. C. Barr ..... 385,228
Photographic developing box, portable, T. W. Harvey ..... 385,264
Photographic sheet, I. Cohn ..... 385,297
Piano case, A. F. Delano ..... 385,172
Pill or lozenge machine, G. A. Smith ..... 385,326
Pinchers, W. E. White ..... 385,030
Pipe coupling, Stewart & Stone ..... 385,148
Pipe coupling, J. Story ..... 385,287
Pipe coupling, automatic, J. F. McElroy ..... 384,991
Pipe covering, H. W. Johns ..... 385,119
Plane, J. A. Bissegger ..... 385,231
Planing maching, wood, J. Ross ..... 385,284
Plant support, potted, F. S. Fahnestock ..... 385,174
Plow, Ball & Bender ..... 384,952
Plow, Thompson & Secrist ..... 385,216
Plow, adjustable double, A. A. Billingslea ..... 385,294
Plow, garden, W. H. Heard ..... 385,051
Plumber's traps, device for making, A. Boll ..... 384,956
Polishing apparatus for wood, etc., T. Davids ..... 385,171
Portfolio, G. Auth ..... 385,085
Potato digger, C. Roberts ..... 385,071
Potato sorter or grader, H. D. Herrington ..... 385,114
Press. See Baling press. Cotton press. Hand press.
Printer's standing galley, W. Severin ..... 385,144
Printing, M. D. Wilkins ..... 385,081
Printing envelopes, blank attachment for tympan sheets for, G. F. Kimball ..... 385,060
Printing machine, C. B. Cottrell ..... 385,099
Printing machines, inking apparatus for, C. B. Cottrell ..... 385,098
Printing machines, sheet delivery apparatus for, C. B. Cottrell ..... 385,100
Propulsion, marine, W. M. Jackson ..... 385,182 to 385,184
Pump, J. North ..... 385,319
Pump attachment, T. Diffley ..... 385,004
Pumping apparatus, electrical, F. J. Sprague ..... 385,211
Punch, paper, J. C. Jensen ..... 385,056
Quilting frame, C. A. Vestal ..... 385,078
Rack. See Hat and coat rack.
Rail joint, G. N. Hodgdon ..... 385,116
Railway cables, driving drum for, F. A. J. Beigel ..... 385,230
Railway, electric, G. H. Condict ..... 385,097
Railway, electric, R. M. Hunter ..... 385,053 to 385,055, 385,180
Railway, electro-motive, G. T. Woods ..... 385,034
Railway frog, G. W. Parsons ..... 385,066
Railway signal, electric, S. C. C. Currie ..... 384,962
Railway spike, J. S. Fox ..... 385,107
Railway switch, L. Blackstone ..... 384,955
Railway switch, S. B. Sabens ..... 385,141
Railway track and joint, B. S. Doran ..... 385,253
Railways, cable gripping apparatus for street, J. H. Dale ..... 385,246
Rake. See Hay rake.
Refrigerator, A. I. Dexter ..... 384,965
Refrigerator, C. A. Bluhm ..... 385,089
Register. See Cash register.
Regulator. See Gas pressure regulator. Tooth regulator.
Rein holder, F. W. C. Macdonald ..... 384,988
Revolvers, extracting mechanism for, D. H. Rice. 385,009
Rheostat, J. W. Packard ..... 385,001
Ring. See Finger ring.
Rivet burr remover, E. H. Perkins ..... 385,133
Rod cutter, H. V. Robinson ..... 385,139
Rolling articles of metal, die for, D. E. Kempster. 385,186
Roof, R. J. Claflin ..... 384,961
Roofing fabric, A. Jones ..... 385,057
Rotary cylinder engine, J. S. Barden ..... 385,226
Rolls, apparatus for removing and setting, W. R. Jones ..... 385,058
Rubber fountains, etc., stopper for, A. C. Eggers. 385,256
Rule, level, and plumb, combined, C. Adkins ..... 384,951
Salt drier, C. T. Bartlett ..... 384,953
Salve, J. R. Smith ..... 385,210
Saw, A. Weymar ..... 385,079
Saw, circular, D. N. Hurd ..... 384,979
Saw guide, adjustable, D. J. Murray ..... 385,131
Saw jointer and gauge, combined, W. S. Ralya ..... 385,006
Saw sharpening machine, R. M. Pine ..... 385,004
Saw swage and sharpener, W. H. Williams ..... 385,290
Scale, weighing and price, J. E. Pitrat ..... 385,005
Scales, weight recorder for weighing, J. A. Jamieson ..... 385,310
Scraper, J. C. Pequinot ..... 385,003
Scraper, track, H. H. Littell ..... 385,062
Scutching or fiber cleaning machines, feeding apparatus for, A. H. Death ..... 385,300
Seal for checks, safety, A. M. Woodhull ..... 385,158
Seat. See Velocipede seat.
Secondary battery, A. Reckenzaun ..... 385,200
Sewing machine for connecting soles and uppers, P. A. & J. Coupal ..... 385,299
Shafts and ordnance, manufacture of, J. H. Flagler ..... 385,049
Shaping machine, Davison & Buckley ..... 384,963
Shell, M. Von Forster ..... 385,332
Shoe tongue fastening, C. F. Crowell ..... 385,045
Sickle grinder, Gamble & Rutt ..... 385,176
Signal. See Marine signal. Railway signal.
Signal compensator, J. J. Turner ..... 385,025
Signaling apparatus, semaphore, A. Barnes ..... 385,227
Sleigh runner, E. K. Van Gorden ..... 385,289
Snap hook, H. McPherson ..... 384,992
Soap and glycerine, making resin, Domeier & Hagemann ..... 385,105
Sofa and surgical table, combined, Judy & Forbes 385,311
Soil pipe ventilator, Hadfield & McConnell ..... 385,262
Spectacles or eyeglasses, frame for, F. A. Henninger ..... 385,307
**Spring. See Car spring. Vehicle spring.**
Sprinkling lawns, device for, E. J. H. Richardson. 385,069
Stairway, T. Rogers ..... 385,012
Stalls, mat for horse, L. S. Stowe ..... 385,149
Station indicator, B. W. Lyon ..... 385,314
Steam boiler, P. Hanrez ..... 384,972
Steam engine, Grabner & Ruperti ..... 385,113
Steam trap and boiler feeder, W. Simpkin ..... 385,014
Steering apparatus for vessels, B. A. Fiske ..... 385,259
Stirrup, T. J. Taylor ..... 385,150
Stocking suspender clip, F. E. Taylor ..... 385,330
Stockings, manufacturing, Morley & Greenwood ..... 385,315
Stove, cook, C. Rathbone ..... 385,135
Stove, gas, W. Moore ..... 385,277
Stovepipe thimble, A. Staub ..... 385,212
Stove polish, C. Zimmerling ..... 385,335
Strainer, A. Boss ..... 385,235
Strainer, drink, C. B. Hopkins ..... 384,977
Strainer, milk, A. Bowdish ..... 385,091
Straw stacker, M. Heinecke ..... 384,974
Supporter. See Garment supporter. Lantern supporter.
Switch. See Electric switch. Railway switch.
Tag, T. J. Yund ..... 385,083
Tank. See Flushing tank. Measuring tank.
Tanning process, W. Zahn ..... 385,222
Teaching of notation and numeration, apparatus to facilitate the, W. E. Carr ..... 384,959
Telegraph relay, Stitzel & Weinedel ..... 385,214
Tile and roofing plate, illuminating, J. Jacobs ..... 385,270
Tile, drain, H. H. Baltzley ..... 385,292
Tile, illuminating, J. Jacobs ..... 385,268, 385,269
Tile, side wall, etc., illuminating, J. Jacobs ..... 385,271
Time ball, C. Muller ..... 384,996
Tobacco, apparatus for treating leaf, G. W. Brooks ..... 385,088
Tooth regulator, W. S. How ..... 385,117
Toy money box, C. A. Bailey ..... 385,225
Trap. See Animal trap. Steam trap.
Traveling bag, A. C. Frankel ..... 384,969
Truck, M. Huntley ..... 385,181
Truck, car, L. K. Jewett ..... 384,981, 384,982
Trucks, safety guard for car, W. H. Walker ..... 385,155
Trunk, W. J. Large ..... 385,189
Trunk lift and strap fastening, combined, G. Crouch ..... 385,242
Tube and making the same, Garver & Straight ..... 385,109
Tube welding apparatus, J. Hemphill ..... 384,975
Type writing machine, F. A. Remley ..... 385,008
Valve, balanced governor, P. S. Kingsland ..... 385,273
Vehicle dash screen, J. H. Murphy ..... 384,997
Vehicle, jump seat, C. H. Stratton ..... 385,329
Vehicle, self-propelling, C. Benz ..... 385,057
Vehicle, spring, T. L. Sturtevant ..... 385,019
Vehicle spring, P. H. Whiting ..... 385,334
Vehicles, spring seat for, L. Warren ..... 385,033
Velocipede, J. E. Evans ..... 385,258
Velocipede, M. H. Marlin ..... 384,990
Velocipede, T. Redman ..... 385,136
Velocipede seat, T. B. Jeffery ..... 384,980
Ventilator. See Soil pipe ventilator.
Vulcanizing apparatus and other purposes, automatic regulator for, O. B. Brann ..... 385,236
Water closet, W. S. Cooper ..... 385,167, 385,168
Water closet structure, W. S. Cooper ..... 385,169
Water closet system, H. S. Miller ..... 385,130
Water heater, G. W. Lewton ..... 385,276
Water, means for utilizing the current force of running, C. M. Garrison ..... 385,261
Water wheel governor, J. Morton ..... 385,280
Wave power motor, F. Starkenberg ..... 385,327
Weather strip, T. K. Milroy ..... 385,065
Weighing and registering apparatus, automatic grain, L. C. Tryon ..... 385,024
Welding, apparatus for electric, E. Thomson ..... 385,022
Well drilling machine, J. F. Moore ..... 384,994
Wheel. See Paddlewheel.
Winding roll for winding paper and other fabrics, J. Waldron ..... 385,026
Windmills, pump rod for, D. B. Nettz ..... 384,998
Wire annealing apparatus, F. H. Daniels ..... 385,247
Wire bending and forming machine, S. T. Newman ..... 384,999
Wire bending implement, D. W. Norris ..... 385,318
Wire netting, B. Scarles ..... 385,143
Woodworking and planing machine, E. H. Lee ..... 385,125
Wringer. See Mop wringer.
Zinc, amalgamating, E. M. Hewett ..... 385,309

## DESIGNS.

Badge, E. A. Crawford ..... 18,407
Burial casket, L. Stein ..... 18,413
Carpet sweeper casing, W. J. Drew ..... 18,408
Educational model, U. G. Houston ..... 18,409
Envelopes, back of, J. Stern ..... 18,414
Game tablets, ornamentation of, J. W. Spalding, 18,411, 18,412
Pen and pencil case, T. Richards ..... 18,410
Quilting, C. T. Wagner ..... 18,415, 18,416

## TRADE MARKS.

Beer, Cramer & Kersten ..... 15,634
Beer, J. Schlitz Brewing Company ..... 15,646
Clother pins, Tobyhanna and Lehigh Lumber Company ..... 15,648
Coal and coke, Jumbo Coal and Coke Co ..... 15,641
Cocoa, soluble, Bensdorp & Co ..... 15,629
Extracts, perfumes, oils, and soaps, Bloomingdale & Levy ..... 15,631 to 15,633
Eye water, E. Billsland ..... 15,630
Glucose, grape sugar, and corn sirup, American Glucose Company ..... 15,627
Lard, Rohe & Brother ..... 15,645
Medicated food for animals, F. E. Sanborn ..... 15,639
Medicinal preparation for uterine diseases, Dios Chemical Company ..... 15,638
Medicine, tonic, J. M. Alloways ..... 15,626
Medicine, tonic, H. Ballantine ..... 15,628
Metal articles for decoration and for toilet and table use, Miller & Berry ..... 15,642
Paper in sheets and pads, blotting, H. S. Crocker & Co ..... 15,636
Paper, water closet, H. S. Crocker & Co ..... 15,635, 15,637
Remedy, Indian blood, H. H. Hopkins ..... 15,640
Stoves, liquid polish for, I. H. Reddic ..... 15,644
Vinegar, Thal & Howe ..... 15,647
Washing machines, Reckagel & Co ..... 15,643

**A Printed copy** of the specification and drawing of any patent in the foregoing list will be furnished from this office for 25 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York.

**Canadian Patents** may now be obtained by the inventors for any of the inventions named in the foregoing list, provided they are simple, at a cost of $40 each. If complicated, the cost will be a little more. For **full instructions address Munn & Co., 361 Broadway, New York. Other foreign patents may also be obtained.**


## Advertisements.

**Inside Page, each insertion - - - 75 cents a line.**
**Back Page, each insertion - - - $1.00 a line.**

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.

**SEBASTIAN, MAY & CO'S**
Improved Screw Cutting
**Foot & Power LATHES**


Drill Presses, Chucks, Drills, Dogs, and machinists' and amateurs' outfits. *Lathes on trial.* Catalogues mailed on application.
**165 W. 2d St., Cincinnati, O.**

GOVERNMENT BREEDING FARM FOR Cavalry Horses.—A paper by Lieut. S. C. Robertson, U. S. A., outlining a plan for the establishment of a breeding farm for horses maintained and controlled by the government, and discussing the economic features of the scheme. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **606.** Price 10 cents. To be had at this office and from all newsdealers.


**ARTESIAN**
Wells, Oil and Gas Wells, drilled by contract to any depth, from 5c to 3000 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 600 ft. Send 6 cents for illustrated catalogue.
**Pierce Well Excavator Co. New York.**

SYSTEMS OF DISTRIBUTION OF Electricity.—A lecture by Elihu Thomson, delivered in the Sibley College course. The series, multiple arc, series multiple and multiple series, accumulator and induction systems described, and their advantages and disadvantages discussed. With 18 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **603.** Price 10 cents. To be had at this office, and from all newsdealers.

**MACHINISTS' SUPPLIES** LATHES CHUCKS TOOLS DRILLS SCREWS CALLIPERS ETC
SEND 13 CENTS FOR ILLUSTRATED CATALOGUE
MONTGOMERY & CO 105 FULTON ST. N.Y.

THE PHONOGRAPH.—A DETAILED description of the new and improved form of the phonograph just brought out by Edison. With 8 engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **632.** Price 10 cents. To be had at this office and from all newsdealers.


**INGERSOLL ROCK DRILL CO.,**
**10 PARK PLACE, NEW YORK.**
**Improved "Eclipse" ROCK DRILLS,**
For Mining, Tunneling, Shaft-Sinking, Quarrying, Submarine drilling, and for all kinds of rock excavation.
"Straight Line" AIR COMPRESSORS, Boilers, Steam and Horse Power Hoists, Electric Blasting Batteries and General Mining Machinery
Send for full descriptive Catalogue

THE DEVELOPMENT OF THE MERcurial Air Pump.—By Prof. Silvanus P. Thompson, D.Sc. An interesting historical paper in which the various mercurial air pumps in use from early times up to the present are classified and described. I. Upward driving pumps. II. Downward driving pumps. III. Upward and downward driving pumps. IV. Combination pumps. V. Injector pumps. VI. Mechanical mercurial pumps. With 36 engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, Nos. **629, 630** and **631.** Price 10 cents each. To be had at this office and from all newsdealers.

**ROCK DRILLS**

**AIR COMPRESSORS &**
GENERAL MACHINERY FOR
MINING, TUNNELING, QUARRY & RAILROAD WORK.
**RAND DRILL Co** 23 PARK PLACE NEW YORK

HISTORY OF THE ELECTRICAL ART in the U. S. Patent Office.—By C. J. Kintner. An interesting history of the growth of electrical science in this country, and notices of some of the more important models in possession of the Patent Office. Contained in SCIENTIFIC AMERICAN SUPPLEMENT No. **544.** Price 10 cents. To be had at this office and from all newsdealers.


**PRINT Your Own CARDS** PRESS $3. Circular size $8. Newspaper size $44. Type setting easy, printed directions. Send 2 stamps for catalogue presses, type, cards, &c., to factory, KELSEY & CO. Meriden, Conn.

AIR, PURIFICATION OF.—BY D. Prince, M.D. An experimental study in relation to the removal from the air of the dust or particulate material, supposed to produce yellow fever, small-pox, and other infectious disease. 1 illustration. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **569.** Price 10 cents. To be had at this office and from all newsdealers.

Fine Taps and Dies, Bolt Cutters, and Labor Saving Tools
**Wiley & Russell Mfg. Co., Greenfield, Mass.**

LIMITING NUMBERS OF TEETH IN Gear Wheels.—A valuable paper by George B. Grant treating of the different methods of determining the limiting numbers of teeth in gear wheels when small pinions must be used. The cycloidal system. The interchangeable volute system. The non-interchangeable volute system. Unreversible teeth. With 11 figures. Contained in the SCIENTIFIC AMERICAN SUPPLEMENT, No. **592.** Price 10 cents. To be had at this office and from all newsdealers.




**ELECTRIC LIGHT AND POWER.**
Edco system of Arc and Incandescent Lighting. Direct or in connection with the Storage Batteries of the Electrical Accumulator Co. Dynamos, Motors, Lamps, Batteries, and General Electrical Supplies.
**THE ELECTRO DYNAMIC COMPANY,**
**224 Carter Street, Philadelphia, Pa.**


© 1888 SCIENTIFIC AMERICAN, INC.

**HENRY CAREY BAIRD & CO.**
**Industrial Publishers, Booksellers, and Importers,**
**810 Walnut St., Philadelphia, Pa., U. S. A.**
☞Our new and Revised Catalogue of Practical and Scientific Books, 80 pages, 8vo, and our other Catalogues and Circulars, the whole covering every branch of Science applied to the Arts, sent free and free of postage to any one in any part of the world who will furnish his address.

# ARCHITECTURAL BOOKS.
## Useful, Beautiful, and Cheap.

To any person about to erect a dwelling house or stable, either in the country or city, or any builder wishing to examine the latest and best plans for a church, school house, club house, or any other public building of high or low cost, should procure a complete set of the ARCHITECTS' AND BUILDERS' EDITION of the SCIENTIFIC AMERICAN.

The information these volumes contain renders the work almost indispensable to the architect and builder, and to persons about to build for themselves they will find the work suggestive and most useful. They contain colored plates of the elevation, plan, and detail drawings of almost every class of building, with specification and approximate cost.

Four bound volumes are now ready and may be obtained, by mail, direct from the publishers or from any newsdealer. Price, $2.00 a volume. Stitched in paper covers. Subscription price, per annum, $2.50. Address and remit to

**MUNN & CO., Publishers,**
**361 Broadway, New York.**




**Hydraulic Elevators**
—AND—
**WATER MOTORS.**
Send for New Catalogue.
**Tuerk Hydraulic Power Co.**
**12 Cortlandt St., New York,**
**39 Dearborn St., Chicago.**

ELECTRIC WELDING.—A PAPER BY Prof. Elihu Thomson, giving an account of a new way of utilizing the heating effects of heavy electrical currents for causing union between pieces of metal, whether of the same or of different kinds. With 4 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **592.** Price 10 cents. To be had at this office and from all newsdealers.



**THE CUSHMAN KEY DRILL CHUCK.**
This is an improvement over all other chucks of its class and is fully guaranteed.

| | DIAM. HOLDS | PRICE |
|---|---|---|
| No. 1, | 2 in. 0 to ½ in. | $6.50 |
| No. 2, | 2½ in. 1-64 to ⅝ in. | 8.00 |

Sold by the trade and Manufactured by THE CUSHMAN CHUCK CO., Hartford, Conn.

PANAMA CANAL.—A PAPER BY DR. W. Nelson on some of the difficulties to be overcome in the prosecution of this work. Damming the Chagres River. Extent of the earth cutting. Ocean tides. The climate. Prevalent diseases. Cost of the canal in lives. Cost of the work. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **603.** Price 10 cents. To be had at this office and from all newsdealers.

**WATER MOTORS.**

The most efficient and economical means of obtaining from one-eighth to fifteen horse power and upward. A motor which does the greatest amount of work with the use of the smallest stream of water, specially adapted for running cheaply and efficiently, Printing Presses, Elevators, Church Organs, Coffee Mills, Sewing Machines, Lathes, Dental Contrivances, and in fact, any piece of Mechanism.
**Binghamton Hydraulic Power Co.,** 182 State Street, **Binghamton, N. Y.**

WOOL HAT MAKING.—FULL DESCRIPTION of the process.—Wool washing, carding and forming, settling, pumping and washing out, stretching or stumping, drying, storing and steaming, pulling out, dyeing, blocking, storing, pressing, finishing, rounding, curling and ironing, paring, trimming and shaping, velouring off. With 20 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, NOS. **626, 628,** and **629.** Price 10 cents each. To be had at this office and from all newsdealers.



**A PRACTICAL SUCCESS.**
**VAN DUZEN'S PAT. LOOSE PULLEY OILER.**
Thousands in satisfactory every-day use. Entire reliability and constancy demonstrated in a two years' test by (would be) Eastern skeptics. Economy shown by reasonable prices and perfect performance. Send for our "Catalogue No. 55."
VAN DUZEN & TIFT, Cincinnati, O

**BELKNAP'S LITTLE GIANT WATER MOTOR**
Is the Best and Cheapest in existence. Send for circulars and price list. AGENTS WANTED. GEO. W. BROWN, General Agent, 10 Milk Street, Portland, Maine.

TRAMWAY, FLEXIBLE GIRDER.—DESCRIPTION of an improved system of constructing a modification of the well known and extensively used rope or wire tramway. With 21 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **595.** Price 10 cents. To be had at this office and from all newsdealers.

GAS ENGINEERING, RECENT PROGRESS in.—By A. Macpherson. Regenerative system of retort firing. Improvements in gas purification. Burners and regenerative lamps. The Welsbach gas light, Paraffin as a rival of coal gas, oil in gas making. Prices of residual products. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **601.** Price 10 cents. To be had at this office and from all newsdealers.

**PERFECT NEWSPAPER FILE**
The Koch Patent File, for preserving newspapers, Magazines, and pamphlets, has been recently improved and price reduced. Subscribers to the SCIENTIFIC AMERICAN and SCIENTIFIC AMERICAN SUPPLEMENT can be supplied for the low price of $1.50 by mail, or $1.25 at the office of this paper. Heavy board sides; inscription "SCIENTIFIC AMERICAN" in gilt. Necessary for every one who wishes to preserve the paper. Address
MUNN & CO., Publishers SCIENTIFIC AMERICAN.

**CURE for the DEAF** by PECK'S PAT. IMPROVED CUSHIONED EAR DRUMS. Whispers heard distinctly. Comfortable, invisible. Illustrated book & proofs, FREE. Address or call on F. HISCOX, 853 Broadway, N. Y. Name this paper.



**WEITMYER PATENT FURNACE**
**BOILERS OF EVERY DESCRIPTION.**
**IDE Automatic Engines, Traction and Portable Engines**
**STEAM ROAD ROLLERS.**
**Manufactured by Foundry and Machine Department,**
Harrisburg, Pa., U. S. A.

CASTING METALS UPON COMBUSTIBLE Materials.—A paper by A. E. Outerbridge Jr., describing a process of casting iron and other metals upon lace, embroideries, fern fronds, and other combustible materials. With 4 illustrations. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **601.** Price 10 cents. To be had at this office and from all newsdealers.

# CHARTER'S GAS ENGINE.
2 to 25 H. P.

The Simplest, most Reliable, and Economical Gas Engine in existence.
An impulse at every revolution. Perfect steadiness guaranteed for Arc or Incandescent Electric Lights.
Independent of gas works when desired, and **makes its own gas** at a cost of **65 cents per M feet,** or about **one cent per hour to each indicated H. P.**
**A Perfectly Safe Motor for All Places and Purposes.**
New York Agent, JOHN J. BOCKIE, 47 Dey Street.
Chicago Agent, H. H. LATHAM, 318 Dearborn Street.
**Williams & Orton Mfg. Co.**
**P. O. Box 148. STERLING, ILL.**

STORAGE BATTERIES FOR ELECTRIC Locomotion.—A paper by A. Reckenzaun, offering a few facts and figures relating to the present state of the subject of the application of storage batteries to locomotive purposes. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **625.** Price 10 cents. To be had at this office and from all newsdealers.

New Otto Rubber Tire
**BICYCLES.**
NO STRONGER BICYCLE MADE.
**A. W. GUMP & CO., Dayton, O.**

| | | | | | |
|---|---|---|---|---|---|
| 52 inch, | factory price | $60.00, | our price | $40.00 |
| 50 | " " | 55.00, | " " | 35.00 |
| 48 | " " | 50.00, | " " | 33.00 |
| 46 | " " | 45.00, | " " | 30.00 |
| 44 | " " | 40.00, | " " | 27.00 |

Order quick. Also 250 second-hand Wheels. Repairing and Nickeling. Bicycles & Guns taken in trade.

**THE BEST WAY** to introduce Patents and Special makes of goods in **Norway** is to advertise in **"The Nationaltidende,"** the only Commercial Paper in Norway, appearing daily in Christiania and established by the Commercial and Maritime Clubs of that city. Each insertion 3d. a line.


**Automatic Cut Off Engines**
Horizontal and Vertical.
Specially adapted for **Electric Lighting. Yacht** and Hoisting Engines. Turbine water wheels. Constructors of Special Machinery of any description.
**YORK MANUF'G CO., YORK, PA., U. S. A.**




PROPULSION OF STREET CARS.—A paper by A. W. Wright, in which an endeavor is made to solve the problem as to the amount of power required to start a street car and keep it in motion under average conditions. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **533.** Price 10 cents. To be had at this office and from all newsdealers.

**Barnes' Patent Foot Power Machinery.**
**WORKERS OF WOOD OR METAL,**
without steam power, by using outfits of these Machines, can bid lower, and save more money from their jobs, than by any other means for doing their work. Also for
**Industrial Schools or Home Training.**
With them boys can acquire practical journeymen's trades before they "go for themselves." Price-List Catalogue Free.
**W. F. & JOHN BARNES CO.,**
No. 1999 Ruby St., Rockford, Ill.

IRRIGATING MACHINERY ON THE Pacific Coast.—By John Richards. An elaborate discussion of the modifications that have had to be made in irrigating machinery to meet the requirements of local conditions in California. Contained in SCIENTIFIC AMERICAN SUPPLEMENT Nos. **624** and **625.** Price 10 cents each. To be had at this office and from all newsdealers.


**BIBB'S Celebrated Original BALTIMORE FIRE-PLACE HEATERS**
**To warm upper and lower rooms The Handsomest and Most Economical Coal Stoves in the world.**
**B. C. BIBB & SON**
**Stove Founders, Baltimore, Md.**
**MARBLEIZED SLATE MANTELS**
New and Beautiful Designs


Makes a perfect Pipe Wrench of any screw wrench. Send for circular. Agents wanted. H. W. ATWATER, P. O. Box 1452, N. Y. City.

**2nd MACHINERY** List Sent.
N. Y. Mach'y Depot, Bridge Store 16, Frankfort St., N.Y.

**PULLEYS, HANGERS, FRICTION CLUTCHES.**
PROGRESS MACHINE WORKS,
A. & F. BROWN,
**44 Park Place, N. Y.**


**ROCK BREAKERS AND ORE CRUSHERS.**
We manufacture and supply at short notice and lowest rates, Stone and Ore Crushers, containing the invention described in Letters Patent issued to Eli W. Blake, June 15th, 1858, together with NEW AND VALUABLE IMPROVEMENTS, for which Letters Patent were granted May 11th and July 20th, 1880, to Mr. S. L. Marsden. All Crushers supplied by us are constructed under the superintendence of Mr. Marsden, who, for the past twenty years, has been connected with the manufacture of Blake Crushers in this country and England.
**FARREL FOUNDRY and MACHINE CO., Manufacturers, Ansonia, Conn.**
**COPELAND & BACON, Agents, NEW YORK and PHILADELPHIA.**

**THE PENNA. DIAMOND DRILL & MFG. CO.**
**BIRDSBORO, PA.,** Builders of High Class Steam Engines, Diamond Drilling and General Machinery. Flour Mill Rolls Ground and Grooved.

**Woodworking Machinery**

FOR
**Chair, Furniture and Cabinet Mills, Pattern Makers' use etc.**
**Rollstone Machine Co.,**
**48 Water Street, Fitchburg, Mass.**

**NO MORE FLIES.** Send 25c. for a sample of the only successful Fly Trap in the world, to Z. XEVERS, 208 Brannan Street, San Francisco, Cal. Also State Rights for sale.

GOING INTO THE POULTRY BUSINESS.—A paper by P. H. Jacobs, reviewing the commercial aspects of poultry raising, and giving many useful hints upon the subject. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **596.** Price 10 cents. To be had at this office and from all newsdealers.

**Put an Electric Bell in your house or shop.**
**You can do it yourself with our Complete Outfit. Price $2 50**
Outfit consists of 1 Electric Bell, 1 Battery, 1 Push Button, 100 feet Wire, and Staples for Wire.
**C. E. JONES & BRO.,**
***55 & 57 Longworth,*** **CINCINNATI, O.**
It is important to us that you mention this paper.

# GUILD & GARRISON
**BROOKLYN, N. Y., U. S. A.**
Builders of **Steam Pumps** for Water and every description of Liquids or Semi-liquids. **Vacuum Pumps** of the highest efficiency. **Filter Press Pumps, Air, Gas, and Acid Blowers. Air Compressors. Boiler Feed Pumps, etc.**

HYPNOTISM IN FRANCE.—AN INTERESTING review of the present status of this subject, by Max Dessoir. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **613.** Price 10 cents. To be had at this office and from all newsdealers.

**WELL** Encyclopedia of 700 Engravings of WELL TOOLS. Diamond Drills and Lightning Hydraulic WELL Machines. Book free, 25c. for mailing it. **WELL** American Well Works, Aurora, Ill.

**$10.00 to $50 00** per night. A light and profitable business. **Magic Lanterns and Views** of popular subjects. Catalogues on application. Part 1 Optical. 2 Mathematical, 3 Meteorological, 4 Magic Lanterns, etc. **L. MANASSE, 88 Madison Street, Chicago, Ill.**

**ICE & REFRIGERATING** Machines. York Patent. **YORK MFG. CO., York, Pa.**

**DELAFIELD'S PAT. SAW CLAMP**

With saw for cutting metals. Saves all the broken hack-saw blades. In use over two years in all parts of the country. The new clamps have the edges bevelled that hold the saw. By mail, with one blade, 50 cents. Extra blades 8½" x ½", "Star," 7 cents each, 70 cents per dozen, by mail. Blades 8" x 1", "Stubs," 35 cents each, by mail. Discount to dealers.
**NOROTON MFG. WORKS, Noroton, Conn.**

**BIT** Square, Oval, or Round Smooth Holes. For carpenter, cabinet, and pattern work, ½ in. 50c., set $4.00, mailed free. Bridgeport Gun Implement Co., 17 Maiden Lane, N. Y.

**A NEW CATALOGUE OF VALUABLE PAPERS**
Contained in SCIENTIFIC AMERICAN SUPPLEMENT, sent *free of charge* to any address.
**MUNN & CO., 361 Broadway, New York.**

**OIL WELL SUPPLY CO. Ltd.**

**91 & 92 WATER STREET,**
**Pittsburgh, Pa.,**
Manufacturers of everything needed for
**ARTESIAN WELLS**
for either Gas, Oil, Water, or Mineral Tests, Boilers, Engines, Pipe, Cordage, Drilling Tools, etc. Illustrated catalogue, price lists and discount sheets on request.


**A Successful Man with a Patent.**
I sell Patents for Inventors. I give for reference the people who buy the state and county rights of me and those I sell the Patents for. I make a success.
Address **F. A. MABEE, Crete, Nebraska.**

**BARREL MACHINERY.**
**E. & B. HOLMES,**
BUFFALO, N. Y.

LEAD SMELTING.—A FULL DESCRIPTION of the Lewis Bartlett process, by William Ramsay; illustrated with 9 engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **593.** Price 10 cents. To be had at this office and from all newsdealers.

**Scientific Book Catalogue**
**RECENTLY PUBLISHED.**
Our new catalogue containing over 100 pages, including works on more than fifty different subjects. Will be mailed free to any address on application.
**MUNN & CO.,** Publishers Scientific American,
**361 Broadway, New York.**

**Proposals for Steel for Use in the Construction of the United States Armored Battle Ship "Texas" at the Navy Yard, Portsmouth, Virginia.**—NAVY DEPARTMENT, WASHINGTON, D. C., *June* 21, 1888.—Under authority conferred by an act of Congress, entitled "An act to increase the naval establishment," approved August 3, 1886 (24 Statutes at Large, page 215), sealed proposals are hereby invited, and will be received at this Department until 12 o'clock noon on Monday, the 23d day of July, 1888 for furnishing the following classes of material for use in the construction of said ship: CLASS A.—*Steel plates.*—About nine hundred and twenty (920) tons of steel plates from 2½ to 25 pounds per square foot. CLASS B.—*Steel shapes.*—About five hundred and three (503) tons of steel shapes, as follows: About two hundred and seventy (270) tons of angle-bars of various sizes; about one hundred and thirty-two (132) tons of angle and T-bulb beams, with proper curvature, from 11 to 24½ pounds per lineal foot; about ten (10) tons of T-bars, of 8 pounds per lineal foot; about ninety-one (91) tons of channel-bars, of 10, 15, and 25 pounds per lineal foot. CLASS C.—*Steel rivets.*—About one hundred (100) tons of steel rivets from ⅝ inch to 1¼ inch diameter. CLASS D.—*Steel castings.*—About one hundred and twenty (120) tons of steel castings, of various shapes, including stem, stern-post, hawse-pipes, riding and mooring bitts, chain-pipes, etc. The tons of material herein called for to be of 2,240 pounds each. All said material to be of such detailed dimensions, weights, and shapes as may be required in the construction of the vessel, and to be delivered at such place or places in the Navy Yard, Portsmouth, Virginia, as may be designated by the Commandant of said Yard. Deliveries to commence within thirty (30) days from the date of contract, and to be completed within six (6) months from such date; the material to be delivered promptly, in accordance with a detailed schedule prepared by the Assistant Naval Constructor at said Navy Yard, and in the order required to carry on the work to the best interests of the Government. All material to be of domestic manufacture, and to be accepted only after passing such tests as may be prescribed therefor by the Secretary of the Navy. Proposals must be in accordance with forms which will be furnished on application to the Bureau of Construction and Repair, and may be for one or more of the classes designated, but no bid for a portion of any class will be considered. Each proposal must be accompanied by satisfactory evidence that the bidder is able to furnish and deliver the material for which he bids. Each proposal must be accompanied by a certified check, payable to the order of the Secretary of the Navy, for an amount equal to five per cent. of the bid. The check received from the successful bidder will be returned to him on his entering into a formal contract for the due performance of the work, and giving bond for the same, with satisfactory surety, in a penal sum equal to twenty-five per cent. of the amount of his bid; but in case he shall fail to enter into such contract and to give such bond within twenty days after notice of the acceptance of his proposal, the check accompanying such proposal shall become the property of the United States. All checks accompanying proposals which are not accepted will be returned immediately after the award shall have been made. Information relative to the dimensions and shapes of material, and all other information essential to bidders, will be furnished on personal application to the Bureau of Construction and Repair, Navy Department. Proposals must be made in duplicate, and inclosed in envelopes marked "Proposals for Steel for the Armored Battleship 'Texas,'" and addressed to the Secretary of the Navy, Navy Department, Washington, D. C. Each class of materials will be bid for separately, and the Secretary of the Navy reserves the right to reject any or all bids or the bids on any class or classes, as, in his judgment, the interests of the Government may require.
D. B. HARMONY, *Acting Secretary of the Navy.*


**WELLS BROTHERS & CO.,**
**GREENFIELD, MASS.**
Manufacturers of Screw Cutting Machinery and Tools, Fine Taps, Adjustable Dies, Bolt Cutters and Nut Tappers. New Little Giant Screw Plates, &c., &c., &c.
Send for Descriptive Catalogue Free.

# TO BUSINESS MEN.
The value of the SCIENTIFIC AMERICAN as an advertising medium cannot be overestimated. Its circulation is many times greater than that of any similar journal now published. It goes into all the States and Territories, and is read in all the principal libraries and reading rooms of the world. A business man wants something more than to see his advertisement in a printed newspaper. He wants circulation. This he has when he advertises in the SCIENTIFIC AMERICAN. And do not let the advertising agent influence you to substitute some other paper for the SCIENTIFIC AMERICAN, when selecting a list of publications in which you decide it is for your interest to advertise. This is frequently done, for the reason that the agent gets a larger commission from the papers having a small circulation than is allowed on the SCIENTIFIC AMERICAN.
For rates see top of first column of this page, or address
**MUNN & CO., Publishers,**
**361 Broadway, New York.**

**FRANCE.** LOUIS LAPFERER, 12 rue Orleans St. Honoré, Paris. Commission Merchant, buys American, electrical and mechanical goods. Inventions. New York references. Correspondence solicited.

**TAKE THE MONON ROUTE BETWEEN**
Chicago and Indianapolis, Cincinnati, and all winter cities of Florida and the South.
LOUISVILLE, NEW ALBANY & CHICAGO RY.
**E. O. McCormick, Gen. Pass. Agent, Chicago.**

**FOR SALE.**—U. S. and English Patents on Metallic Knockdown Box. Superior to wooden boxes. U. S. Pat. No. 371,322, Eng. Pat. No. 16,724. Correspondence solicited with manufacturers. Address JOHN HOTHAM, Hillside, Westmoreland Co., Pa.

**FOR SALE.** City, County, or State Rights, under Patent 340,454. Address Duplex Gas Regulator Co., P. O. Box 940, or 31 Broadway, New York.

# VALUABLE PATENT
## FOR SALE.
A rare opportunity for a good business man with ample capital to engage in the manufacture of a staple article, which has already proven its merits. This will bear the closest investigation. Address **R. M. FULTON, Room 23, German Am. Bank Building, St. Paul, Minn.**

**The Scientific American**
**PUBLICATIONS FOR 1888.**

The prices of the different publications in the United States, Canada, and Mexico are as follows:

RATES BY MAIL.

| | |
|---|---|
| The Scientific American (weekly), one year | $3.00 |
| The Scientific American Supplement (weekly), one year. | 5.00 |
| The Scientific American, Export Edition (monthly) one year, | 5.00 |
| The Scientific American, Architects and Builders Edition (monthly), one year. | 2.50 |

COMBINED RATES.

| | |
|---|---|
| The Scientific American and Supplement, | $7.00 |
| The Scientific American and Architects and Builders Edition, | 5.00 |
| The Scientific American, Supplement, and Architects and Builders Edition, | 9.00 |

*Proportionate Rates for Six Months.*

This includes postage, which we pay. Remit by postal or express money order, or draft to order of
**MUNN & CO., 361 Broadway, New York.**

ELIXIR Grows Full Beard, Moustache and Hair in 20 days. Man, Woman, Girl or Boy. Anybody $5 a day. We mail a $5 size OUTFIT FREE for 50c. in stamps to pay charges. Smith Manf. Co., Palatine, Ills.

© 1888 SCIENTIFIC AMERICAN, INC.

## Advertisements.

**Inside Page, each insertion - - - 75 cents a line.**
**Back Page, each insertion - - - $1.00 a line.**

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.

These Hack Saws will cut Iron and Steel beyond all expectation.

Iron working mechanics everywhere must and will use them. They do the work of files at one-tenth the cost, and in one-tenth the time. One Patent Nickel-plated Steel frame, and one dozen 8 inch Blades, sent by mail, prepaid, on receipt of $1.50. Hardware dealers will furnish them at at the same price. All saws marked with a star, and bearing our name are fully warranted.

**MILLERS FALLS CO.,**
***93 Reade Street, New York***

**MALLEABLE** AND FINE GRAY IRON ALSO STEEL CASTINGS FROM SPECIAL PATTERNS
THOMAS DEVLIN & CO. FINE TINNING JAPANNING AND FINISHING
LEHIGH AVE. & AMERICAN ST. PHILA.

GLACIAL EPOCHS AND THEIR PERIODICITY.—By Adolphe d'Assier. A presentation of the considerations that tend to establish the fact that the progressive cooling of the earth must, in the course of ages, have produced circumpolar glaciers, and that the periodic and alternate return of these in the two hemispheres is closely connected with the secular displacement of the perihelion. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, NOS. **631** and **632**. Price 10 cents each. To be had at this office and from all newsdealers.

# THE AMERICAN BELL TELEPHONE CO.

95 MILK ST., BOSTON, MASS.

This Company owns the Letters Patent granted to Alexander Graham Bell, March 7th, 1876, No. 174,465, and January 30th, 1877, No. 186,787.

The transmission of Speech by all known forms of Electric Speaking Telephones infringes the right secured to this Company by the above patents, and renders each individual user of telephones not furnished by it or its licensees responsible for such unlawful use, and all the consequences thereof, and liable to suit therefor.

# NICKEL PLATING

& POLISHING MATERIALS.
**ZUCKER & LEVETT**
CHEMICAL Co NEW YORK U.S.A

NICKEL ANODES,
NICKEL SALTS,
ROUGES,
COMPOSITION,
BUFFING WHEELS,
ELECTRO & NICKEL
PLATING OUTFITS.

HOW TO MAKE AN INCUBATOR.—Full directions, illustrated with 7 figures. Also directions for operating the apparatus. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **612**. Price 10 cents. To be had at this office and from all newsdealers.



**WHITE MOUNTAIN**
**Hammock Chair.**

For the House, Lawn, Porch, and Camp. Is chock full of Comfort and Blessed Rest.

**PRICE, $3.00.**
**The Alford & Berkele Co.**
**77 Chambers St.**
P. O. Box 2002. NEW YORK.

# PATENTS.

MESSRS. MUNN & CO., in connection with the publication of the SCIENTIFIC AMERICAN, continue to examine improvements, and to act as Solicitors of Patents for Inventors.

In this line of business they have had *forty-one years' experience*, and now have *unequaled facilities* for the preparation of Patent Drawings, Specifications, and the prosecution of Applications for Patents in the United States, Canada, and Foreign Countries. Messrs Munn & Co. also attend to the preparation of Caveats, Copyrights for Books, Labels, Reissues, Assignments, and Reports on Infringements of Patents. All business intrusted to them is done with special care and promptness, on very reasonable terms

A pamphlet sent free of charge, on application, containing full information about Patents and how to procure them; directions concerning Labels, Copyrights, Designs, Patents, Appeals, Reissues, Infringements, Assignments, Rejected Cases, Hints on the Sale of Patents, etc.

We also send, *free of charge*, a Synopsis of Foreign Patent Laws, showing the cost and method of securing patents in all the principal countries of the world.

**MUNN & CO., Solicitors of Patents,**
361 Broadway, New York.

BRANCH OFFICES.—No. 622 and 624 F Street, Pacific Building, near 7th Street, Washington, D. C.

# THE GUTTA PERCHA & RUBBER MFG. CO.

The Largest Manufacturers of Mechanical Rubber Goods in the World.
**ESTABLISHED 1855.**
**Packing, Belting, Hose, Mats, Matting, etc.**
**New York, Chicago, San Francisco, Portland, Oregon.**

## The Original Unvulcanized Packing.

CALLED THE STANDARD—As it is the Packing by which all others are compared.

Accept no packing as JENKINS PACKING unless stamped with our "Trade Mark."

**JENKINS BROS.** { 71 John Street, N. Y. / 105 Milk Street, Boston. / 18 So. Fourth St., Phila. / 54 Dearborn St., Chicago.

**SAWS** Wanted 50,000 Sawyers and Lumbermen to send us their full address for a copy of Emerson's Book of **SAWS**. We are first to introduce NATURAL GAS for heating and tempering **Saws** with wonderful effect upon improving their quality and toughness, enabling us to reduce prices. Address **SAWS**
**EMERSON, SMITH & CO. (Ltd.), Beaver Falls, Pa.**

INVENTORS and others desiring new articles manufactured and introduced, address P. O. Box 86, Cleveland, O.

JAMES B. EADS.—AN ACCOUNT OF the life and labors of this eminent engineer. With a portrait. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **592**. Price 10 cents. To be had at this office and from all newsdealers.

H. E. MATHEWS'
**LICK OBSERVATORY VIEWS**
**PHOTOS.**
Send 50 cts. for sample. 331 Montg. R, 20. San Francisco.

HOME-MADE INCUBATOR.—PRACTICAL directions for the manufacture of an effective incubator that has been carefully tested and found to perform all that may be reasonably expected; with directions for operating. With 4 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **630**. Price 10 cents. To be had at this office and from all newsdealers.

# STEEL BALLS.

**For Anti-Friction Bearings, of Best Cast Steel. Hardened, Ground, and Burnished,** from 3-16 in. to 2 in. diameter.

In quality and density of metal, in uniformity of temper, and in accuracy and nicety of finish warranted unequaled.

☞ *Samples and prices on application.*

**Simond's Rolling-Machine Co., Fitchburg, Mass.**

# GAS ENGINES.

Best in principle, workmanship, and materials.
An unequaled small Motor adapted to all uses.
When the motor is not at work, the expense of running it ceases.
**Simple, Safe, Economical, Durable. No extra insurance.**
Four sizes: 1 H. P., ½ H. P., 1 man power, and Dental Engine.
These Engines are especially suited for Gasoline Gas for country use.
☞ *Send for Illustrated Catalogue.*



**ECONOMIC GAS ENGINE COMPANY,**
**Office and Salesrooms - - 34 DEY ST. N. Y.**

## THE DUNNING PATENT WROUGHT IRON BOILER.

(Over 13,500 in use.)



THE Dunning Boiler, Self-Feeding, is the best for Low Pressure Steam Heating, and insures a warm house night and day. Free from Carbonic Acid Gas and Smoke. Made in eleven sizes, suitable to heat the **Smallest Cottage to the Largest Business Block,** in five different styles:

As a Magazine Boiler, which requires attention but once in twenty-four hours.

As a Surface Burning Boiler, which will burn Hard or Soft Coal, Wood, Coke or Gas.

As a Hot Water Boiler, for Green House and hot water heating.

As a Portable Boiler, to be set without brickwork.

Also in **Two Sections**, to pass through any door or window, where whole one cannot enter. Steam Engines and Boilers of all kinds and machinery generally. Manufactured at the **New York Central Iron Works, Geneva, N. Y., U.S.A.** Lock Box 40. *Send for New Illustrated Catalogue.*

Trade Mark.

## MAGNESIA SECTIONAL STEAM-PIPE AND BOILER COVERINGS.

THE MAGNESIA SECTIONAL **Covering Co.** PHILADELPHIA.
**Local Agents Wanted Everywhere.**




# Steam! Steam!

We build Automatic Engines from 2 to 200 H. P., equal to anything in market.

**A Large Lot of 2, 3, and 4-H. Engines**
With or without boilers, **low for cash,**
**B. W. PAYNE & SONS,**
Box 15, **Elmira, N. Y.**

# WATCHMAKERS

**Send for REDUCED PRICE LIST of Whitcomb Lathes,** date of July 1, 1888. American Watch Tool Co., Waltham, Mass.

FIRE-BRICK.—BY R. A. COOK, A.M. An interesting description of the mining of fire clay and the manufacture of fire brick at Mt. Savage, Maryland where is located one of the largest establishments in the country devoted to this industry. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **538**. Price 10 cents. To be had at this office and from all newsdealers.

# WIRE ROPE

Address JOHN A. ROEBLING'S SONS, Manufacturers, Trenton, N. J., or 117 Liberty Street, New York.
Wheels and Rope for conveying power long distances. Send for circular.

ICE-HOUSE AND COLD ROOM.—BY R. G. Hatfield. With directions for construction. Four engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, **59**. Price 10 cents. To be had at this office and of all newsdealers.

## Novelty Hot Air Furnaces.

**Expose an Immense Heated Surface.**

Extract all the Heat from the Gases. Furnish Pure Warm Air in Abundance.

Fourteen Years of Test. Universally satisfactory.

Send for "Our Furnace Book."

**Abram Cox Stove Co.,**
MANUFACTURERS,
Philadelphia and Chicago.





# New Gas Engine "The Baldwin"

*Exhibited at the late American Institute Fair, New York.*

A four horse-power engine in connection with storage battery, running 84 incandescent electric lights (and without battery, 32 lights), giving a perfect light, with all the steadiness that can be obtained from the high-speed steam engines in common use for electric lighting, and permitting any number of lights to be shut off or turned on without affecting the remaining lights in the slightest degree. A marvel of beauty, perfection, and power, adapted to lighting, pumping, and all purposes where a safe and cheap power is required. Manufactured and guaranteed by

**Otis Brothers & Co.**
**Elevators and Hoisting Machinery,**
**38 PARK ROW, NEW YORK.**

# ICE and REFRIGERATING MACHINES

**The Pictet Artificial Ice Company (Limited), Room 6, Coal & Iron Exchange, New York.**

# CHALLENGE EMERY GRINDING POLISHING MACHINERY

DIEBEL MFG. CO. THIRD AND CUMBERLAND PHILA.

THE COPYING PAD.—HOW TO MAKE and how to use; with an engraving. Practical directions how to prepare the gelatine pad, and also the aniline ink by which the copies are made; how to apply the written letter to the pad; how to take off copies of the letter. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **438**. Price 10 cents. For sale at this office and by all newsdealers in all parts of the country.

# SYRACUSE MALLEABLE IRON WORKS

W. B. BURNS PROP'R

INFLUENCE MACHINES.—A PAPER by James Wimshurst, giving a complete account of the recent forms of generators of static electricity. With 13 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **647**. Price 10 cents. To be had at this office and from all newsdealers.

# AUTOMATIC CUT OFF ENGINES PERFECTLY GOVERNED

MANUFACTURED UPON SCIENTIFIC AND PRACTICAL PRINCIPLES
BALL ENGINE CO. ERIE PA.

# BRASS WORK

**Small Brass Work & Models** A Specialty,
**Also Nickel Plating.**
**T. L. McKEEN,**
**Easton, Penn.**

TELESCOPES—THEIR HISTORY and the discoveries made with them.—By Prof. E. S. Holden. An interesting historical paper, discussing the development of the telescope from the time of Galileo up to the present day. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **629**. Price 10 cents. To be had at this office and from all newsdealers.

SEAMLESS BRASS & COPPER TUBES, SHEET BRASS, BRASS WIRE
MACHINISTS' TOOLS, TAPS, DIES, REAMERS, ETC.
SEND FOR CATALOGUE
175-177 LAKE ST. CHICAGO.

Mention this paper.

# THE Scientific American

**ESTABLISHED 1846.**

**The Most Popular Scientific Paper in the World.**

**Only $3.00 a Year, including Postage. Weekly. 52 Numbers a Year.**

**This widely circulated** and splendidly illustrated paper is published weekly. Every number contains sixteen pages of useful information and a large number of original engravings of new inventions and discoveries, representing Engineering Works, Steam Machinery, New Inventions, Novelties in Mechanics, Manufactures, Chemistry, Electricity, Telegraphy, Photography, Architecture, Agriculture, Horticulture, Natural History, etc. Complete List of Patents each week.

**Terms of Subscription.**—One copy of the SCIENTIFIC AMERICAN will be sent for *one year*—52 numbers—postage prepaid, to any subscriber in the United States or Canada, on receipt of **three dollars** by the publishers; six months, $1.50; three months, $1.00.

**Clubs.**—Special rates for several names, and to Post Masters. Write for particulars.

The safest way to remit is by Postal Order, Draft, or Express Money Order. Money carefully placed inside of envelopes, securely sealed, and correctly addressed, seldom goes astray, but is at the sender's risk. Address all letters and make all orders, drafts, etc., payable to

**MUNN & CO.,**
**361 Broadway, New York.**

# THE Scientific American Supplement.

This is a separate and distinct publication from THE SCIENTIFIC AMERICAN, but is uniform therewith in size, every number containing sixteen large pages full of engravings, many of which are taken from foreign papers, and accompanied with translated descriptions. THE SCIENTIFIC AMERICAN SUPPLEMENT is published weekly, and includes a very wide range of contents. It presents the most recent papers by eminent writers in all the principal departments of Science and the Useful Arts, embracing Biology, Geology, Mineralogy, Natural History, Geography, Archæology, Astronomy, Chemistry, Electricity, Light, Heat, Mechanical Engineering, Steam and Railway Engineering, Mining, Ship Building, Marine Engineering, Photography, Technology, Manufacturing Industries, Sanitary Engineering, Agriculture, Horticulture, Domestic Economy, Biography, Medicine, etc. A vast amount of fresh and valuable information obtainable in no other publication.

*The most important Engineering Works*, Mechanisms, and Manufactures at home and abroad are illustrated and described in the SUPPLEMENT.

Price for the SUPPLEMENT for the United States and Canada, $5.00 a year, or one copy of the SCIENTIFIC AMERICAN and one copy of the SUPPLEMENT, both mailed for one year for $7.00. Single copies 10 cents. Address and remit by postal order, express money order, or check,

**MUNN & Co., 361 Broadway, N. Y.,**
Publishers SCIENTIFIC AMERICAN.

# Builders Edition.

THE SCIENTIFIC AMERICAN ARCHITECTS' AND BUILDERS' EDITION is issued monthly. $2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming a large and splendid **Magazine of Architecture,** richly adorned with *elegant plates in colors*, and with other fine engravings; illustrating the most interesting examples of modern Architectural Construction and allied subjects.

A special feature is the presentation in each number of a variety of the latest and best plans for private residences, city and country, including those of very moderate cost as well as the more expensive. Drawings in perspective and in color are given, together with full Plans, Specifications, Sheets of Details, Estimates, etc.

The elegance and cheapness of this magnificent work have won for it the **Largest Circulation** of any Architectural publication in the world. Sold by al newsdealers. $2.50 a year. Remit to

**MUNN & CO., Publishers,**
**361 Broadway, New York.**

# PRINTING INKS.

THE "Scientific American" is printed with CHAS. ENEU JOHNSON & CO.'S INK. Tenth and Lombard Sts., Phila., and 47 Rose St., opp. Duane St., N. Y.

© 1888 SCIENTIFIC AMERICAN, INC.